

FILE NAME = I:\6611\661124 - Fuller-ton over Silver Creek\CAADD\CADD\04\04shets\0162006-500.dgn

| CODE NO. | ITEM   | UNIT   | TOTAL QUANTITY | CONSTR. CODE |             |
|----------|--|--------|----------------|--------------|-------------|
|          |  |        |                | ROADWAY 0004 | BRIDGE 0011 |
|          |  |        |                | URBAN        | URBAN       |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER)        | UNIT   | 189            | 189          |             |
| 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER)        | UNIT   | 40             | 40           |             |
| 20101100 | TREE TRUNK PROTECTION                        | EACH   | 10             | 10           |             |
| 20200100 | EARTH EXCAVATION                             | CU YD  | 2332           | 2332         |             |
| 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL  | CU YD  | 599            | 371          | 228         |
| 20300100 | CHANNEL EXCAVATION                           | CU YD  | 464            | 464          |             |
| 20700220 | POROUS GRANULAR EMBANKMENT                   | CU YD  | 286            |              | 286         |
| 20800150 | TRENCH BACKFILL                              | CU YD  | 114            | 114          |             |
| 21001000 | GEOTECHNICAL FABRIC FOR GROUND STABILIZATION | SQ YD  | 683            |              | 683         |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4"                | SQ YD  | 3611           | 3611         |             |
| 21400100 | GRADING AND SHAPING DITCHES                  | FOOT   | 794            | 794          |             |
| 25000210 | SEEDING, CLASS 2A                            | ACRE   | 0.75           | 0.75         |             |
| 25000400 | NITROGEN FERTILIZER NUTRIENT                 | POUND  | 67             | 67           |             |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT               | POUND  | 67             | 67           |             |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT                | POUND  | 67             | 67           |             |
| 25100630 | EROSION CONTROL BLANKET                      | SQ YD  | 3611           | 3611         |             |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING            | POUND  | 75             | 75           |             |
| 28000305 | TEMPORARY DITCH CHECKS                       | FOOT   | 190            | 190          |             |
| 28000400 | PERIMETER EROSION BARRIER                    | FOOT   | 1282           | 1282         |             |
| 28000510 | INLET FILTERS                                | EACH   | 11             | 11           |             |
| 28100107 | STONE RIPRAP, CLASS A4                       | SQ YD  | 175            |              | 175         |
| 28200200 | FILTER FABRIC                                | SQ YD  | 175            |              | 175         |
| 28500100 | FABRIC FORMED CONCRETE REVETMENT MATS        | SQ YD  | 96             | 96           |             |
| 35501308 | HOT-MIX ASPHALT BASE COURSE, 6"              | SQ YD  | 394            | 394          |             |
| 40600100 | BITUMINOUS MATERIALS (PRIME COAT)            | GALLON | 646            | 646          |             |
| 40600300 | AGGREGATE (PRIME COAT)                       | TON    | 13             | 13           |             |
| 40701921 | HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"   | SQ YD  | 2840           | 2840         |             |
| 40603310 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON    | 45             | 45           |             |

| CODE NO. | ITEM  | UNIT  | TOTAL QUANTITY | CONSTR. CODE |             |
|----------|---|-------|----------------|--------------|-------------|
|          |   |       |                | ROADWAY 0004 | BRIDGE 0011 |
|          |   |       |                | URBAN        | URBAN       |
| 42001300 | PROTECTIVE COAT                                     | SQ YD | 931            | 931          |             |
| 42300200 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH  | SQ YD | 138            | 138          |             |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH            | SQ FT | 1982           | 1982         |             |
| 42400410 | PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH            | SQ FT | 399            | 399          |             |
| 42400800 | DETECTABLE WARNINGS                                 | SQ FT | 12             | 12           |             |
| 44000100 | PAVEMENT REMOVAL                                    | SQ YD | 2935           | 2935         |             |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL                           | SQ YD | 397            | 397          |             |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL                 | FOOT  | 226            | 226          |             |
| 44000600 | SIDEWALK REMOVAL                                    | SQ FT | 237            | 237          |             |
| 48101600 | AGGREGATE SHOULDERS, TYPE B 8"                      | SQ YD | 248            | 248          |             |
| 48101620 | AGGREGATE SHOULDERS, TYPE B 10"                     | SQ YD | 140            | 140          |             |
| 48203029 | HOT-MIX ASPHALT SHOULDERS, 8"                       | SQ YD | 664            | 664          |             |
| 50104400 | CONCRETE HEADWALL REMOVAL                           | EACH  | 3              | 3            |             |
| 50100100 | REMOVAL OF EXISTING STRUCTURES                      | EACH  | 1              |              | 1           |
| 50105220 | PIPE CULVERT REMOVAL                                | FOOT  | 306            | 306          |             |
| 50200100 | STRUCTURE EXCAVATION                                | CU YD | 1414           |              | 1414        |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED                    | POUND | 105,040        |              | 105,040     |
| 51500100 | NAME PLATES   | EACH  | 1              |              | 1           |
| 54003000 | CONCRETE BOX CULVERT                                | CU YD | 577.6          |              | 577.6       |
| 542A0229 | PIPE CULVERTS, CLASS A, TYPE 1 24"                  | FOOT  | 74             | 74           |             |
| 542A1069 | PIPE CULVERTS, CLASS A, TYPE 2 24"                  | FOOT  | 48             | 48           |             |
| 542D0220 | PIPE CULVERTS, CLASS D, TYPE 1 15"                  | FOOT  | 172            | 172          |             |
| 54213450 | END SECTIONS 15"                                    | EACH  | 8              | 8            |             |
| 54213459 | END SECTIONS 24"                                    | EACH  | 2              | 2            |             |
| 54213660 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15" | EACH  | 1              | 1            |             |
| 54213669 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24" | EACH  | 5              | 5            |             |
| 54247100 | GRATING FOR CONCRETE FLARED END SECTION 15"         | EACH  | 1              | 1            |             |
| 54247130 | GRATING FOR CONCRETE FLARED END SECTION 24"         | EACH  | 5              | 5            |             |

\* - DENOTES SPECIALTY ITEM



USER NAME = rge11  
 PLOT SCALE = 50,0000 ' / IN.  
 PLOT DATE = 5/27/2011

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

|   |          |        |              |           |
|---|----------|--------|--------------|-----------|
| F.A.U. RTE.                                       | SECTION  | COUNTY | TOTAL SHEETS | SHEET NO. |
| 1381  | 0101.1-T | COOK   | 47           | 3         |
| CONTRACT NO. 60M82                                |          |        |              |           |
| FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT |          |        |              |           |