

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 342	2011-026-I	COOK & LAKE	71	36

CONTRACT NO. 60P26

East Panel No.	Wooden Batten, Secure Existing (LF)	Wooden Batten, Salvage and Reposition (LF)	Wooden Batten, Furnish and Install (LF)	Wooden Plank, Salvage and Reposition (SF)	Wooden Plank, Furnish and Install (SF)	Wooden Wall, Painting (1 Unit = 100 SF)	Porous Granular Material (CU YD)	Comments (All Panel had 4 vertical battens unless otherwise noted)
367	50	7			6			19' Panel Height, 76' total Batten Length, 3 vertical battens
368	48		28		48			19' Panel Height
369	62	10			12			18' Panel Height, 72' total Batten Length
370	46	26			24			
371	72				48			18' Panel Height
372	50	26			96			19' Panel Height, 76' total Batten Length, 3 vertical battens
373	64	12			84			
374	64	12			72			19' Panel Height, 76' total Batten Length, 3 vertical battens
375	52		24		90			20' Panel Height, 80' total Batten Length
376	52		28		78			
377	56		24		84			All bottom replaced due to bowing of wall
378	42	14	24		72			
379	52	28			78			20' Panel Height, OK No bowing
380	60							20' Panel Height, 3' WIDE
381	53		7		27			20' Panel Height, 3' WIDE
382	40	26	14		90			20' Panel Height
383	38	35	7		120			
384	66	7	7		84			
385	56		24	18	72			All bottom replaced due to bowing of wall
386	52		24		60			19' Panel Height, 76' total Batten Length, 3 vertical battens
387	51	19	6		84			19' Panel Height
388	50	26			60			
389	50	6	20		72			
390	76				84			
391	16		56		96			All bottom replaced due to bowing of wall
392	48		28		108			All bottom replaced due to bowing of wall
393	48		28		102			All bottom replaced due to bowing of wall

ILLINOIS DEPARTMENT OF
TRANSPORTATION

SCHEDULE OF QUANTITIES
SHEET 31 OF 36