



U.S. RTE. 34

RAMP FROM S.B. IL. RTE. 83

RAMP C

RAMP D

RAMP TO S.B. IL. RTE. 83

(BARE CONCRETE RESURFACING)
POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX 'F', N90, 1 3/4"
POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19, N90, 2 1/4"

(BARE CONCRETE RESURFACING)
POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX 'F', N90, 1 3/4"
POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19, N90, 2 1/4"

(SHOULDER RESURFACING)
HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N70, 1 1/2"
HOT-MIX ASPHALT BINDER COURSE, IL-19, N70, 2 1/2"

PROPOSED GUARDRAIL REMOVAL (31.25 FT ONLY)
PROPOSED TRAFFIC BARRIER TERMINAL, TYPE 6

3 OVER OGDEN AVE.

S.B. IL. RTE. 83

N.B. IL. RTE. 83

RAMP F

LEGEND

- ① THERMOPLASTIC PAVEMENT MARKING
EDGE LINE, 4" SOLID WHITE
- ② THERMOPLASTIC PAVEMENT MARKING
EDGE LINE, 4" SOLID YELLOW
- ③ THERMOPLASTIC PAVEMENT MARKING
4" SOLID DOUBLE YELLOW
- ④ THERMOPLASTIC PAVEMENT MARKING
6" SOLID WHITE TURN LANE LINE
- ⑤ THERMOPLASTIC PAVEMENT MARKING
8" SOLID WHITE GORE LINE
- ⑥ THERMOPLASTIC PAVEMENT MARKING
24" WHITE STOP BAR
- ⑦ THERMOPLASTIC PAVEMENT MARKING
LETTER & SYMBOLS
- ⑧ THERMOPLASTIC PAVEMENT MARKING
4" WHITE SKIP DASH
- ⑨ THERMOPLASTIC PAVEMENT MARKING
12" SOLID WHITE DIAGONAL LINE

NOTE:
*REMOVE ALL GUARDRAIL WITHIN RESURFACING LIMITS.
REMOVE A PORTION OF THE GUARDRAIL OUTSIDE RESURFACING LIMITS
TO TRANSITION TO STANDARD MINIMUM HEIGHT.

FILE NAME =	USER NAME = abreuh	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ROADWAY AND PAVEMENT MARKING PLANS IL. ROUTE 83 AT US ROUTE 34 (RAMP 'C' & 'D')				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\dot\abreuh\d0265704\DI519	11-sh-t-plan.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	DUPAGE	33	12
		CHECKED -	REVISED -		CONTRACT NO. 60P34								
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								