



**NOTE:**  
 \*REMOVE ALL GUARDRAIL WITHIN RESURFACING LIMITS.  
 REMOVE A PORTION OF THE GUARDRAIL OUTSIDE RESURFACING LIMITS  
 TO TRANSITION TO STANDARD MINIMUM HEIGHT.

**LEGEND**

- ① THERMOPLASTIC PAVEMENT MARKING  
EDGE LINE, 4" SOLID WHITE
- ② THERMOPLASTIC PAVEMENT MARKING  
EDGE LINE, 4" SOLID YELLOW
- ③ THERMOPLASTIC PAVEMENT MARKING  
4" SOLID DOUBLE YELLOW
- ④ THERMOPLASTIC PAVEMENT MARKING  
6" SOLID WHITE TURN LANE LINE
- ⑤ THERMOPLASTIC PAVEMENT MARKING  
8" SOLID WHITE GORE LINE
- ⑥ THERMOPLASTIC PAVEMENT MARKING  
24" WHITE STOP BAR
- ⑦ THERMOPLASTIC PAVEMENT MARKING  
LETTER & SYMBOLS
- ⑧ THERMOPLASTIC PAVEMENT MARKING  
4" WHITE SKIP DASH
- ⑨ THERMOPLASTIC PAVEMENT MARKING  
12" SOLID WHITE DIAGONAL LINE

FILE NAME =	USER NAME = ebrauh	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>ROADWAY AND PAVEMENT MARKING PLAN IL. ROUTE 38 AT YORK RD. (RAMP L &amp; M)</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\p\work\p1\dot\ebrauh\d0265704\DI51511-sht-plan.dgn		DRAWN -	REVISED -		SCALE: 1"=50'	SHEET NO.	OF	SHEETS	STA.	TO STA.	DUPAGE	33	17
		CHECKED -	REVISED -								CONTRACT NO.	60P34	
		DATE -	REVISED -								ILLINOIS FED. AID PROJECT		