

DATE	
BY	
PLAN	
SURVEYED	
ALIGNMENT CHECKED	
RT. OF WAY CHECKED	
NO. FILE NAME	
NOTE BOOK	
NO.	

DATE	
BY	
PLAN	
SURVEYED	
ALIGNMENT CHECKED	
RT. OF WAY CHECKED	
NO. FILE NAME	
NOTE BOOK	
NO.	

TREE REMOVAL 6 TO 15 UNITS DIAMETER		
STATION		UNITS INCHES
491+33	RT	7
491+91	LT	14
492+00	LT	12
493+04	LT	14
493+20	LT	14
493+33	LT	7
494+28	RT	9
495+79	LT	8
495+81	LT	7
496+72	LT	12
496+73	LT	12
496+75	RT	14
498+32	LT	12
498+40	LT	12
499+24	RT	7
501+32	RT	14
501+33	LT	8
501+54	LT	9
501+86	RT	14
501+89	RT	14
502+32	LT	9
503+86	RT	12
504+46	LT	12
505+52	LT	13
505+72	LT	9
505+72	LT	9
505+72	LT	9
506+17	LT	12
506+22	RT	7
506+72	LT	14
506+72	LT	14
506+96	RT	7
506+96	RT	7
507+03	RT	8
507+06	LT	9
507+28	LT	14
507+51	RT	7
507+57	RT	7
507+57	RT	7
507+93	RT	7
508+11	RT	7
508+11	RT	7
508+11	RT	7
508+59	RT	12
508+85	RT	7
509+01	RT	7
509+23	RT	7
509+24	RT	8
509+30	RT	7
509+62	RT	8
509+79	RT	9
510+35	RT	7
510+52	RT	10
510+65	RT	8
510+69	LT	7
510+82	RT	7
511+30	LT	14
511+34	RT	12
511+51	RT	7
511+59	RT	7
511+66	LT	12
511+75	RT	9

TREE REMOVAL 6 TO 15 UNITS DIAMETER		
STATION		UNITS INCHES
511+75	RT	12
512+07	LT	15
512+28	RT	8
512+55	LT	9
512+68	LT	13
512+89	LT	10
513+37	LT	7
513+37	LT	7
513+49	LT	12
513+51	LT	8
513+55	LT	14
513+64	LT	7
513+64	LT	7
513+94	LT	8
514+09	LT	7
514+15	LT	7
514+17	LT	7
514+18	RT	13
514+23	LT	8
514+47	RT	9
514+47	RT	9
514+69	RT	7
514+71	RT	7
514+72	RT	12
514+85	RT	14
515+26	RT	10
515+26	RT	10
515+26	RT	10
515+45	RT	9
515+59	RT	10
515+59	RT	10
515+67	LT	13
515+67	LT	13
515+72	RT	7
515+79	RT	12
515+84	RT	10
515+84	RT	10
515+84	RT	10
515+90	LT	9
515+90	LT	9
516+06	LT	15
516+17	RT	12
516+18	RT	9
516+23	RT	12
516+34	RT	9
516+35	LT	15
516+41	RT	9
516+41	LT	14
516+44	LT	15
516+46	LT	9
516+52	RT	12
516+70	LT	12
516+71	RT	12
516+71	RT	12
516+75	LT	14
516+77	RT	9
516+92	RT	7
516+93	RT	7
517+05	RT	7
517+05	RT	7
517+08	RT	12
517+09	RT	12
517+10	RT	12

TREE REMOVAL 6 TO 15 UNITS DIAMETER		
STATION		UNITS INCHES
517+24	RT	7
517+32	RT	12
517+33	RT	7
517+51	RT	9
517+68	RT	7
518+04	RT	7
518+23	RT	7
518+28	RT	14
518+44	RT	7
518+50	RT	7
518+53	RT	7
518+81	RT	7
519+98	LT	9
521+11	RT	7
521+27	RT	7
521+74	RT	14
521+77	RT	14
522+01	RT	7
522+03	RT	7
522+90	RT	7
523+11	RT	7
523+32	RT	14
523+36	RT	7
523+82	RT	9
524+18	RT	14
524+52	RT	14
524+65	RT	7
526+27	RT	14
526+98	RT	12
527+23	RT	7
527+32	RT	12
527+74	RT	7
528+36	RT	9
529+49	LT	7
529+53	LT	9
530+16	RT	9
530+84	RT	9
531+89	LT	7
532+07	LT	12
SUBTOTAL:		1595
INCREASE SUBTOTAL BY 5%:		80
TOTAL:		1675

TREE REMOVAL OVER 15 UNITS DIAMETER		
STATION		UNITS INCHES
491+85	LT	17
495+91	LT	18
496+23	LT	18
496+57	RT	16
496+73	LT	18
496+74	LT	23
496+84	LT	16
498+35	LT	28
501+99	RT	20
507+34	LT	16
511+18	LT	28
511+46	LT	28
511+57	LT	23
511+79	LT	28
511+93	LT	30
512+07	LT	17
512+21	LT	37
512+33	LT	37
512+36	LT	37
512+90	LT	21
513+10	LT	16
513+19	LT	16
513+26	LT	16
514+39	LT	28
514+39	RT	18
515+54	RT	18
516+45	LT	21
516+75	LT	24
524+93	RT	16
TOTAL:		649

CLEARING, SPECIAL			
STATION	STATION	OFFSET	UNITS ACRES
488+50	490+50	LT	0.13
492+25	494+90	LT	0.19
496+10	497+75	RT	0.13
500+50	506+80	LT	0.50
506+00	512+50	RT	0.51
510+40	514+37	LT	0.30
514+00	519+00	RT	0.40
514+48	517+00	LT	0.17
518+80	520+20	LT	0.11
521+00	525+20	RT	0.33
TOTAL:			3.00

SELECTIVE CLEARING			
STATION	STATION	OFFSET	UNITS
* 490+85	493+85	RT	4.4
* 495+80	497+25	RT	1.5
* 498+60	500+50	RT	1.9
* 506+50	507+25	RT	0.7
* 508+50	513+00	RT	8.0
* 514+00	519+00	RT	5.1
* 520+50	529+00	RT	7.0
TOTAL:			29

* SELECTIVE CLEARING AND/OR TREE REMOVAL SHALL NOT BE PERFORMED UNTIL PARCEL IS OWNED BY IDOT. THE STATIONS LISTED ABOVE MAY INCORPORATE MULTIPLE PARCELS. AT TIME OF BIDDING, THE PARCEL(S) IS NOT YET OWNED BY IDOT.

NOTE:

THE TREE DIAMETERS NOTED ON THE PLAN WERE DETERMINED FROM A TREE SURVEY THAT WAS TAKEN IN 2003. THE PLAN QUANTITIES AND SCHEDULES REFLECT AN ESTIMATED GROWTH OF 15% SINCE THE TREE SURVEY WAS PERFORMED.

Rev. 7-19-11