

GENERAL NOTES:

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS AND GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4 SCHEDULE OF QUANTITIES
- 5 ALIGNMENT, TIES AND BENCHMARKS
- 6-7 TREE REMOVAL PLAN
- 8-13 SUE INVESTIGATION OF UNDERGROUND UTILITIES (FOR INFORMATION ONLY)
- 14-20 PLAT OF HIGHWAYS (FOR INFORMATION ONLY)
- 21 TC-22 DISTRICT ONE ARTERIAL ROAD INFORMATION SIGN

COMMITMENTS

NONE

GENERAL

1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRICAL, TELEPHONE, AND GAS FACILITIES. 48 HOURS NOTIFICATION IS REQUIRED.
2. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH IDOT, THE UTILITY COMPANIES AND THE VILLAGE OF SOUTH BARRINGTON.
3. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
4. WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AS WELL AS ADJOINING RESIDENTIAL AREAS.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
6. THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.
7. THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.
8. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
9. THE CONTRACTOR SHALL CONTACT A REPRESENTATIVE OF THE ROADSIDE DEVELOPMENT UNIT IN THE BUREAU OF MAINTENANCE AT (847) 705-4171 AT LEAST 72 HOURS IN ADVANCE OF SELECTIVE CLEARING AND CLEARING WORK ONLY. ALL LOCATIONS OF ROW, TEMPORARY EASEMENT, CONSTRUCTION LIMITS AND TREE REMOVAL SHALL BE CLEARLY DESIGNATED PRIOR TO LAYOUT WORK.
10. THE TREE DIAMETERS NOTED ON THE PLAN WERE DETERMINED FROM A TREE SURVEY THAT WAS TAKEN IN 2003. THE PLAN QUANTITIES AND SCHEDULES REFLECT AN ESTIMATED GROWTH OF 15% SINCE THE TREE SURVEY WAS PERFORMED.

STATE STANDARDS

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 701001-02 OFF RD OPERATIONS 2L, 2W, MORE THAN 15' (4.5M) AWAY
- 701006-03 OFF-RD OPERATIONS, 2L, 2W, 15' (4.5M) TO 24" (600MM) FROM PAVEMENT EDGE
- 701011-02 OFF RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
- 701201-04 LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS > 45 MPH
- 701301-04 LANE CLOSURE 2L, 2W, SHORT TIME OPERATIONS
- 701901-01 TRAFFIC CONTROL DEVICES

DATE	BY	SURVEYED	CHECKED
		ALIGNMENT	CHECKED
		RT. OF WAY	CHECKED
		GRID FILE NAME	
PLAN	NOTE BOOK	NO.	

DATE	BY	SURVEYED	CHECKED
		ALIGNMENT	CHECKED
		RT. OF WAY	CHECKED
		GRID FILE NAME	
PLAN	NOTE BOOK	NO.	

FILE NAME = ...\\D160P52-sht-gennotes1.dgn



DESIGNED	MHL	REVISED	-
DRAWN	GEW	REVISED	-
CHECKED	RJD	REVISED	-
DATE	MAY 20, 2011	REVISED	-

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL RTE 62 (ALGONQUIN RD.) FROM EASTING'S WAY TO PENNY RD.
INDEX OF SHEET, STATE STANDARDS,
GENERAL NOTES AND COMMITMENTS**

SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
339	2011-043-DTR	COOK	21	2
CONTRACT NO. 60P52			ILLINOIS FED. AID PROJECT	