

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-02-FF	MCHENRY	292	005
STA.		TO STA.		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
CONTRACT NO: 63522				

ITEM NO	DESCRIPTION	UNIT	URBAN TOTAL	CONSTRUCTION TYPE CODE		
				WALKUP RD CMAQ	WALKUP RD STU	WALKUP RD LOCAL
				0003	0003	0043
40600300	AGGREGATE (PRIME COAT)	TON	292	292		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7	4	3	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	90		90	
40600895	CONSTRUCTING TEST STRIP	EACH	3	1	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	157	99	58	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	13974	13974		
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	64		64	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	464	352	112	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3152	3073	79	
40701941	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13"	SQ YD	20540	17279	3261	
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	14025		14025	
42001300	PROTECTIVE COAT	SQ YD	11275	7274	4001	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	181	48	133	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	151	54	97	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	16751		16751	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1319	875	444	
42400800	DETECTABLE WARNINGS	SQ FT	626	227	399	
44000100	PAVEMENT REMOVAL	SQ YD	34030	21398	12632	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	5164	3027	2137	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	9102	3940	5162	
44000600	SIDEWALK REMOVAL	SQ FT	13069	2847	10222	
44200104	PAVEMENT PATCHING, TYPE I, 9 INCH	SQ YD	4			4
44200108	PAVEMENT PATCHING, TYPE II, 9 INCH	SQ YD	45			45
44200114	PAVEMENT PATCHING, TYPE IV, 9 INCH	SQ YD	122			122
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	170	170		
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	671	573	98	
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	61	61		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	18081	17496	585	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	892	892		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	921	921		
50105220	PIPE CULVERT REMOVAL	FOOT	1370	1370		
50200100	STRUCTURE EXCAVATION	CU YD	627		627	
50300225	CONCRETE STRUCTURES	CU YD	477.6		477.6	
50300285	FORM LINER TEXTURED SURFACE	SQ FT	3953		3953	
50500505	STUD SHEAR CONNECTORS	EACH	1056		1056	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	72200		72200	
50901750	PARAPET RAILING	FOOT	465		465	
50901760	PIPE HANDRAIL	FOOT	182		182	
51603000	DRILLED SHAFT IN SOIL	CU YD	20.9		20.9	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	26	26		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	12	12		
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	16	16		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3	3		

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SUMMARY OF QUANTITIES SHEET 2 OF 8

SCALE: N.T.S.
DATE: 06/10/11

DRAWN BY: LK
CHECKED BY: MCD

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
260 N. MICHIGAN AVE. CHICAGO, IL 60611
TELEPHONE: 312.586.9000

I:\S002\A00JDON...S002\A00JDON...809\HAC01JON...S002\A00JDON...TRANS...01\2202\300-03\CIVIL\CAD\02.CONTRACT\A...TENC\SHEET\S002\A002.SHT
6-09-20 11:55:03
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63