

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-02-FP	MCHENRY	292	010
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
CONTRACT NO: 63522				

ITEM NO	DESCRIPTION	UNIT	URBAN TOTAL	CONSTRUCTION TYPE CODE		
				WALKUP RD CMAQ 0003	WALKUP RD STU 0003	WALKUP RD LOCAL 0043
88700300	LIGHT DETECTOR AMPLIFIER	EACH	2			2
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8		8	
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2		2	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1	
89502380	REMOVE EXISTING HANDHOLE	EACH	14		14	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		9	
X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	5540		5540	
X0325714	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	EACH	2	2		
X0327190	STEEL CASING PIPE AUGERED AND JACKED 24"	FOOT	226			226
X2010400	STUMP REMOVAL ONLY	UNIT	200	200		
X2030300	CHANNEL EXCAVATION (SPECIAL)	CU YD	1157		1157	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	162		162	
X2090210	POROUS GRANULAR BACKFILL, SPECIAL	CU YD	182		182	
X2502024	SEEDING, CLASS 4B (MODIFIED)	ACRE	0.7	0.7		
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	48	34	14	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	11	6	5	
X4023000	TEMPORARY ACCESS (ROAD)	EACH	1		1	
X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	6	6		
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	12728	10553	2175	
X5610651	ABANDON EXISTING WATER MAIN, FILL WITH CLSM	FOOT	399			399
X5610748	WATER MAIN LINE STOP 8"	EACH	1			1
X5620030	WATER SERVICE CONNECTION 1"	EACH	22			22
X5630004	CUT AND CAP EXISTING 4" WATER MAIN	EACH	2			2
X6020073	INLETS, TYPE A, TYPE B GRATE, TEMPORARY	EACH	9	6	3	
X6020096	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE I FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	4	2	2	
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	11	6	5	
X6026051	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	4	1	3	
X6064500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (TEMPORARY)	FOOT	4782	3038	1744	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.7	0.3	
X7200105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	475	306	169	
X7200205	SIGN PANEL - TYPE 2 (SPECIAL)	SQ FT	20	20		
X7280105	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)	FOOT	1440	979	461	
X7310110	BASE FOR TELESCOPING SIGN SUPPORT, SPECIAL	EACH	100	68	32	
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	727			727
XX003338	TEST HOLE	EACH	6	3	3	
XX003528	DUCTILE IRON WATER MAIN FITTING - 8" PLUG	EACH	4			4
XX004731	CONNECTION TO EXISTING WATERMAIN	EACH	10			10
XX005230	VIDEO DETECTION SYSTEM COMPLETE INTERSECTION	L SUM	1	1		
XX005855	WATER MAIN CASING PIPE	FOOT	24			24
XX006536	WATER SERVICE LINE 1", BORED	FOOT	396			396
XX006570	TREES (SPECIAL)	EACH	286	286		
XX006613	AGGREGATE SURFACE COURSE, TYPE B 2" (SPECIAL)	SQ YD	283		283	

• SPECIALTY ITEM

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SUMMARY OF QUANTITIES SHEET 7 OF 8

SCALE: N.T.S. DRAWN BY: LK
 DATE: 06/10/11 CHECKED BY: MCD

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
300 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312.587.2000

S:\02\10\01\01\11\12\13\14\15\16\17\18\19\20\21\22\23\24\25\26\27\28\29\30\31\32\33\34\35\36\37\38\39\40\41\42\43\44\45\46\47\48\49\50\51\52\53\54\55\56\57\58\59\60\61\62\63
 STANBUL
 6/16/11 6:06:59 AM