

SCHEDULE OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-02-FR	MCHENRY	292	025
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
CONTRACT NO: 63522				

TOTAL 11 EACH				
60265700 VALVE VAULTS TO BE ADJUSTED				
LOCATION STATION OFFSET				SUBTOTALS
WALKUP	53+00	20.0	LT	1
WALKUP	55+27	28.4	LT	1
WALKUP	59+13	21.0	LT	1
WALKUP	61+03	23.6	LT	1
WALKUP	62+95	24.6	LT	1
WALKUP	75+26	19.0	LT	1
WALKUP	76+08	30.0	LT	1
WALKUP	80+35	24.0	LT	1
WALKUP	80+50	30.5	LT	1
IL 176	47+39	31.3	RT	1
IL 176	44+48	33.6	RT	1

TOTAL 4 EACH				
60266100 VALVE VAULTS TO BE RECONSTRUCTED				
LOCATION STATION OFFSET				SUBTOTALS
WALKUP	53+11	20.0	LT	1
WALKUP	67+00	22.0	LT	1
WALKUP	68+35	19.0	LT	1
IL 176	45+32	30.0	RT	1

STORM SEWER (WATER MAIN REQUIREMENTS)				
PIPE ID	CLASS	A	SIZE	LOCATION LNTH
SS-0407	2		18"	CL 15.0
SS-0408	2		18"	CL 3.0
SS-0416	2		15"	CL 22.0
SS-0502	2		12"	MCDOT 21.0
SS-0503	2		18"	MCDOT 22.0
SS-0505	2		12"	MCDOT 45.0
SS-0510	2		24"	MCDOT 22.0
SS-0511	2		15"	MCDOT 10.0
SS-0515	2		18"	MCDOT 12.0
SS-0519	2		12"	MCDOT 22.0
SS-0521	2		12"	MCDOT 20.0
SS-0601	2		12"	MCDOT 17.0
SS-0603	2		12"	MCDOT 9.0
SS-0605	1		12"	MCDOT 5.0
SS-0700	1		12"	MCDOT 11.0
SS-0705	1		12"	MCDOT 6.0
SS-0706	1		12"	MCDOT 9.0
SS-0709	1		12"	MCDOT 11.0
SS-0711	1		12"	MCDOT 6.0
SS-0712	1		12"	MCDOT 9.0
SS-0714	1		12"	MCDOT 8.0
SS-0715	1		12"	MCDOT 9.0
SS-0718	1		15"	MCDOT 59.0
SS-0719	2		24"	MCDOT 8.0
SS-0721	1		12"	MCDOT 5.0
SS-0723	1		15"	MCDOT 21.0
SS-0727	2		12"	MCDOT 5.0
SS-4007	2		30"	IDOT 22.0
SS-4009	2		12"	IDOT 7.0
SS-4012	2		12"	IDOT 11.0
SS-5008	2		12"	IDOT 36.0
SS-5026	1		15"	IDOT 21.0
SS-5028	1		12"	IDOT 15.0
SS-5030	2		12"	IDOT 5.0
SS-5037	1		12"	IDOT 5.0

TOTAL 286 EACH			
XX006570 TREES (SPECIAL)			
PLANT MATERIAL	LOCATION 1	LOCATION 2	SUBTOTALS
(A2007120) QUERCUS RUBRA (RED OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	18	14	32
(A2006520) QUERCUS BICOLOR (SWAMP WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	18	14	32
(A2002924) CELTIS OCCIDENTALIS (COMMON HACKBERRY), 3" CALIPER, BALLED AND BURLAPPED	18	14	32
(A2008024) TILIA CORDATA (LITTLE LEAF LINDEN), 3" CALIPER, BALLED AND BURLAPPED	18	14	32
(A2006518) ULMUS PARVIFOLIA (LACEBARK ELM), 2" CALIPER, BALLED AND BURLAPPED	18	14	32
(D2002288) PICEA PUNGENS GLAUCA (COLORADO BLUE SPRUCE), 8' HEIGHT, BALLED AND BURLAPPED	18	14	32
(A2001024) ACER RUBRUM (RED MAPLE), 3" CALIPER, BALLED AND BURLAPPED	18	14	32
(A2002520) CARPINUS CAROLINIANA (AMERICAN HORNBEAM), 2-1/2" CALIPER, BALLED AND BURLAPPED	17	14	31
(B2010165) CORNUS KOUSA (KOUSA DOGWOOD), 5' HEIGHT, BALLED AND BURLAPPED	17	14	31

LOCATION 1: NUNDA TOWNSHIP 3510 BAY RD, CRYSTAL LAKE, IL
 LOCATION 2: 100 W. WOODSTOCK STREET, CRYSTAL LAKE, IL

S:\SC02\A002\DCN... \B099\A001\DCN... \S-5-004\AMVA\VAULT.D - TRANS.DT\2202\300-03\CIVIL\CAD\02 CONTRACT\VA - TENG\SHEET\SC02\A002.SHT 5 TANKRUJ
 4-4-2011 15:40:120
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SCHEDULE OF QUANTITIES

SHEET 5 OF 8

SCALE: N.T.S. DRAWN BY: LK
 DATE: 04/15/11 CHECKED BY: MCD

TENG & ASSOCIATES, INC.
 ENGINEERS ARCHITECTS PLANNERS
 305 N. MICHIGAN AVE., CHICAGO, IL 60610
 TELEPHONE: 312.961-8000