



F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-02-FP	MCHENRY	292	046
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
CONTRACT NO: 63522				




STA 298+59.20 LT TO STA 298+00.00 LT

STA 299+00.00 RT TO STA 299+32.08 RT


**CURB TRANSITION DETAIL**




SECTION A-A




SECTION B-B




SECTION C-C




SECTION D-D



SECTION A1-A1



SECTION B1-B1



SECTION A2-A2

- CURB TRANSITION NOTES:**
1. THE THICKNESS OF THE HOT-MIX ASPHALT SHOULDER CONSTRUCTED BETWEEN THE EDGE OF PAVEMENT AND THE COMBINATION CONCRETE CURB AND GUTTER SHALL BE 1/4" GREATER THAN THE ADJACENT COMBINATION CONCRETE CURB AND GUTTER. THE THICKNESS OF THE HOT-MIX ASPHALT SHOULDER SHALL BE 8" AT SECTIONS A-A AND A1-A1 AND SHALL UNIFORMLY TRANSITION TO THE REQUIRED THICKNESS AT SECTION B-B AND B1-B1. THE COST OF THE ADDITIONAL DEPTH OF HOT-MIX ASPHALT SHOULDERS WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR HOT-MIX ASPHALT SHOULDERS, 8".
  2. THE THICKNESS OF THE AGGREGATE SHOULDER SHALL BE 8" AT SECTIONS A-A AND A1-A1 AND SHALL UNIFORMLY TRANSITION TO A THICKNESS OF 6" AT SECTION A2-A2. THE COST OF THE ADDITIONAL THICKNESS OF AGGREGATE SHOULDER WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR AGGREGATE SHOULDERS, TYPE B, 6".
  3. ALL CURB AND GUTTER SHOWN ON THE CURB TRANSITION DETAIL WILL BE PAID FOR AS COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24.

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION  
WALKUP ROAD F.A.J. 0085

**CURB TO SHOULDER  
TRANSITION DETAILS**

SCALE: N.T.S.      DRAWN BY: RJS  
DATE: 04/15/11      CHECKED BY: MCD

**TENG**  
TENG & ASSOCIATES, INC.  
ENGINEERS ARCHITECTS PLANNERS  
300 N. MICHIGAN AVE. CHICAGO, IL 60611  
TELEPHONE: 312.640.6000

DET00\_24JUN..AB999A0000N...AB999A0000N...AB999A0000N...AB999A0000N...AB999A0000N...  
 4-14-2011 10:08:35      STANKRJ      CONTRACT: \\A:\CAD\02 CONTRACT\1\A\_TENG\SHEET\PROB00005.SHT  
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63