F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-02-FP	MCHENRY	292	156
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 63522

SCHEDULE OF EXISTING SIGNS

SIGN ID	ROAD	EXISTING LOCATION STATION	EXISTING LOCATION OFFSET +:RT, -:LT	RELOCATED STATION	RELOCATED OFFSET	SIGN DESCRIPTION	MUTCD CODE	GROUND MOUNTING TYPE	HEIGHT FT	WIDTH FT	AREA SQ. FT	PROP. ACTION	PANEL TYPE	REMOV SIN PAN ASSY TA 72400100	REMOV SIN PAN ASSY TB 72400200	RELOCATE SIGN PANEL TY 1 72400710	RELOCATE SIGN PANEL TY 2 72400720
W-11	WALKUP ROAD	50+27	59			FOLDING STOP	R1-1	TELESCOPING	3.00	3.00	7.45	REMOVE	1	1.00			
W-12	WALKUP ROAD	51+91	26			SPEED LIMIT 30	R2-1	WOODEN POST	3.00	2.50	7.50	REMOVE	1	1.00			
W-13A	WALKUP ROAD	52+97	23	53+24	35.0	MC HENRY COUNTY, ADOPT A HIGHWAY	CUSTOM	TELESCOPING	2.50	2.50	6.25	RELOCATE	1		1.00	6.25	
W-13B	WALKUP ROAD	52+97	23	53+24	35.0	BOY SCOUT TROOP 580	CUSTOM		1.50	2.50	3.75	RELOCATE	1			3.75	
W-14	WALKUP ROAD	63+04	55			VETERAN ACRES PARK	CUSTOM	STONE COLUMNS	4.50	8.50	38.25	REMAIN	3				
W-15	WALKUP ROAD	63+59	63			STOP SIGN	R1-1	TELESCOPING	3.00	3.00	7.45	REMOVE	1	1.00			
W-16	WALKUP ROAD	63+71	53			VETERAN ACRES PARK	CUSTOM	STONE COLUMNS	4.50	8.50	38.25	REMAIN	3				
W-17	WALKUP ROAD	65+00	39			SPEED LIMIT 40	R2-1	TELESCOPING	3.50	2.50	8.75	REMOVE	1	1.00			
W-18	WALKUP ROAD	71+99	41	79+33	39.9	SPEED LIMIT 40	R2-1	TELESCOPING	3.50	2.50	8.75	RELOCATE	1	1.00		8.75	
W-19	WALKUP ROAD	73+93	45	73+92	32.3	PARK HOURS 9A.M TO DUSK	CUSTOM	TELESCOPING	1.50	1.00	1.50	RELOCATE	1	1.00		1.50	
W-20	WALKUP ROAD	76+78	40			WARNING, FIBER OPTIC CABLE	CUSTOM	TELESCOPING	1.00	0.30	0.30	REMAIN	1				
W-21	WALKUP ROAD	77+88	27	77+52	27.5	THROUGH TRAFFIC (LEFT), RIGHT TURN ONLY (RIGHT)	CUSTOM	WOODEN POST	2.50	2.50	6.25	RELOCATE	1	1.00		6.25	
W-22	WALKUP ROAD	80+97	49			STOP SIGN	R1-1	TELESCOPING	3.00	3.00	7.45	REMAIN	1				
W-23A	WALKUP ROAD	81+03	47			STREET SIGN (BURNING BUSH)	CUSTOM	UTILITY POST	0.75	3.00	2.25	REMAIN	1				
W-23B	WALKUP ROAD	81+03	47			STREET SIGN (WALKUP AVE)	CUSTOM	UTILITY POST	0.75	2.50	1.88	REMAIN	1				
W-24	WALKUP ROAD	230+70	23			SPEED LIMIT 45	R2-1	TELESCOPING	3.00	2.50	7.50	REMOVE	1	1.00			
W-25	WALKUP ROAD	233+46	33			OLD TOP FARM, GOLF	CUSTOM	TREE MOUNTED	2.50	2.50	6.25	REMAIN	1				
W-26	WALKUP ROAD	244+98	23			SPEED LIMIT 50	R2-1	TELESCOPING	3.00	2.50	7.50	REMOVE	1	1.00			
W-27	WALKUP ROAD	252+29	28			VILLAGE OF BULL VALLEY	CUSTOM	WOODEN POST	2.00	4.00	8.00	REMAIN	1				
W-28	WALKUP ROAD	254+52	28			RIGHT CURVE	W1-2R	TELESCOPING	3.00	3.00	9.00	REMOVE	1	1.00			
W-29A	WALKUP ROAD	258+37	27			T INTERSECTION	W2-2	WOODEN POST	3.00	3.00	9.00	REMOVE	1		1.00		
W-29B	WALKUP ROAD	258+37	27			STREET SIGN (MASON HILL RD)	CUSTOM	WOODEN POST	0.75	3.00	2.25	REMOVE	1				
W-30	WALKUP ROAD	265+59	39			TWO DIRECTION LARGE ARROW	W1-7	WOODEN POST	2.00	4.00	8.00	REMOVE	1	1.00			
W-31A	WALKUP ROAD	266+22	25	267+28	25.4	MCHENRY COUNTY ADOPT A HIGHWAY	CUSTOM	TELESCOPING	2.50	2.50	6.25	RELOCATE	1		1.00	6.25	
W-31B	WALKUP ROAD	266+22	25	267+28	25.4	IN LOVING MEMORY OF MICHELLE MICHAELIS	CUSTOM		1.50	2.50	3.75	RELOCATE	1			3.75	
W-32	WALKUP ROAD	276+36	26			SPEED LIMIT 50	R2-1	TELESCOPING	3.00	2.50	7.50	REMOVE	1	1.00			
W-33	WALKUP ROAD	293+57	29			NO PASSING ZONE	W14-3	WOODEN POST	4.00	5.00	10.00	REMOVE	2		1.00		
W-34	WALKUP ROAD	296+71	38			CRYSTAL VALLEY EQUINE	CUSTOM	WOODEN POST	3.00	4.00	12.00	REMAIN	2				
W-35	WALKUP ROAD	299+39	26			SPEED LIMIT 50	R2-1	TELESCOPING	3.00	2.50	7.50	REMOVE	1		1.00		
W-36	WALKUP ROAD	299+39	-23			SPEED LIMIT 50	R2-1	TELESCOPING	3.00	2.50	7.50	REMOVE	1				
W-37	WALKUP ROAD	284+03	-28			LEFT CURVE	W1-2L	WOODEN POST	3.00	3.00	9.00	REMOVE	1	1.00			
W-38	WALKUP ROAD	276+38	-29			SPEED LIMIT 50	R2-1	WOODEN POST	3.00	2.50	7.50	REMOVE	1	1.00			
W-39A	WALKUP ROAD	272+39	-29			T INTERSECTION	W2-2	TELESCOPING	3.00	3.00	9.00	REMOVE	1		1.00		
W-39B	WALKUP ROAD	272+39	-29			STREET SIGN (MASON HILL RD)	CUSTOM	TELESCOPING	0.75	3.00	2.25	REMOVE	1				
W-40A	WALKUP ROAD	267+26	-29	270+45	-25.1	MCHENRY COUNTY ADOPT A HIGHWAY	CUSTOM	TELESCOPING	2.50	2.50	6.25	RELOCATE	1		1.00	6.25	
W-40B	WALKUP ROAD	267+26	-29	270+45	-25.1	YOUR GROUP NAME HERE	CUSTOM		1.50	2.50	3.75	RELOCATE	1			3.75	
W-41A	WALKUP ROAD	265+76	-36			STREET SIGN (MASON HILL RD)	CUSTOM	TELESCOPING	1.00	4.00	4.00	REMOVE	1	1.00			
W-41B	WALKUP ROAD	265+76	-36			STREET SIGN (CRYSTAL LAKE RD)	CUSTOM	TELESCOPING	1.00	4.00	4.00	REMOVE	1				
W-42A	WALKUP ROAD	265+65	-65	265+64	-87.2	WEIGHT LIMIT 8 TONS	R12-1	WOODEN POST	2.50	2.00	5.00	RELOCATE	1	1.00		5.00	
W-42B	WALKUP ROAD	265+65	-65	265+64	-87.2	OVERWEIGHT VEHICLE AND RALLY	CUSTOM	WOODEN POST	2.00	1.50	3.00	RELOCATE	1			3.00	
W-42C	WALKUP ROAD	265+64	-65	265+64	-87.2	VILLAGE OF BULL VALLEY	CUSTOM	WOODEN POST	2.00	4.00	8.00	RELOCATE	1	1.00		8.00	
W-43A	WALKUP ROAD	265+63	-66			SPEED LIMIT 50	R2-1	WOODEN POST	2.50	2.00	5.00	REMOVE	1	1.00			
W-43B	WALKUP ROAD	265+63	-66	265+64	-87.2	SOLICTORS PERMIT REQUIRED	CUSTOM	WOODEN POST	1.00	1.50	1.50	RELOCATE	1			1.50	
W-44	WALKUP ROAD	265+19	-42			STOP SIGN	R1-1	WOODEN POST	3.00	3.00	7.45	REMOVE	1	1.00			
W-45	WALKUP ROAD	264+89	-68			GOLF 27 HOLES, GOLF CLUB & LEARNING CENTER	CUSTOM	WOOD POSTS	6.30	2.30	14.49	REMAIN	2				
W-46	WALKUP ROAD	254+85	-36			CENTURY RIDGE FARM	CUSTOM	TREE MOUNTED	3.00	2.00	6.00	REMAIN	1				
W-47	WALKUP ROAD	249+68	-36	248+88	-30.3	RAINTREE DR	CUSTOM	TELESCOPING	0.75	2.50	1.88	RELOCATE	1	1.00		1.88	
W-48A	WALKUP ROAD	249+47	-133			WEIGHT LIMIT 5 TONS	R12-1	TELESCOPING	2.50	2.00	5.00	REMAIN	1				
W-48B	WALKUP ROAD	249+47	-133			NO PARKING ON TOWNSHIP ROADS	CUSTOM	TELESCOPING	2.00	1.50	3.00	REMAIN	1				
W-49	WALKUP ROAD	249+47	-133			SPEED LIMIT 25	R2-1	TELESCOPING	2.50	2.00	5.00	REMAIN	1				
W-50	WALKUP ROAD	249+04	-40			STOP SIGN	R1-1	TELESCOPING	3.00	3.00	7.45	REMOVE	1	1.00			
W-51	WALKUP ROAD	245+00	-22			SPEED LIMIT 45	R2-1	TELESCOPING	3.00	2.50	7.50	REMOVE	1	1.00			
W-52	WALKUP ROAD	239+45	-27			REVERSE CURVE	W1-4R	TELESCOPING	3.00	3.00	9.00	REMOVE	1	1.00			
W-53	WALKUP ROAD	236+53	-31	235+78	-29.1	COACHLIGHT RD	CUSTOM	TELESCOPING	0.75	2.00	1.50	RELOCATE	1	1.00		1.50	
W-54A	WALKUP ROAD	236+43	-82			NO PARKING ON TOWNSHIP ROADS	CUSTOM	TELESCOPING	2.00	1.50	3.00	REMAIN	1				

• SEE NOTE 4 ON SHEET 173 FOR PROPOSED ACTION.

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SIGNING SCHEDULE
EXISTING CONDITIONS
SHEET 2 OF 3

SCALE: N.T.S. DRAWN BY: MN

DATE: 04/15/11 CHECKED BY: MM

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
300 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0300

..\S02A003.DGN,..\S02A003.DGN,..\B99WA00L.DGN,..\S02A009.SHT STANKRJ
4:14:20W,15:35:51 \\FS-004\AMY\VAULT\D-TRANS_DT\2202\300-03\CIVIL\CAD\02 CONTRACT\A-TENG\SHEET\S02A000.SHT
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63