F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-02-FP	MCHENRY	292	158
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 63522

SCHEDULE OF PROPOSED SIGNS

SIGN ID	ROAD	PROPOSED LOCATION STATION	PROPOSED LOCATION OFFSET (FT) + : RT - : LT	MUTCD CODE	SIGN DESCRIPTION	GROUND MOUNTING TYPE	HEIGHT FT	WIDTH FT	AREA SQ. FT	PANEL TYPE	SIGN PANEL TYPE 1 (SPECIAL)	SIGN PANEL TYPE 2 (SPECIAL)	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)***	BASE FOR TELESCOPING SIGN SUPPORT (SPECIAL)	METAL POST TYPE A
											X7200105	X7200205	X7280105	X7310110	72900100
T-101	IL ROUTE 176	47+60	48.6	R3-5R	RIGHT TURN ONLY	TELESCOPING	3.00	2.50	7.50	1	7.50		15	1	
T-102	IL ROUTE 176	52+68	52.0	R1-1	STOP SIGN	TELESCOPING	3.00	3.00	7.45	1	7.45		15	1	
T-103	IL ROUTE 176	53+39	35.9	R2-1	SPEED LIMIT 30	TELESCOPING	3.00	2.50	7.50	1	7.50		14	1	
T-104	IL ROUTE 176	54+80	40.6	W9-2L	LANE ENDS, MERGE LEFT	TELESCOPING	3.00	3.00	9.00	1	9.00		14	1	
T-105	IL ROUTE 176	56+55	45.8	R1-1	STOP SIGN	TELESCOPING	3.00	3.00	7.45	1	7.45		14	1	
T-106	IL ROUTE 176	59+76	44.4	R1-1	STOP SIGN	TELESCOPING	3.00	3.00	7.45	1	7.45		14	1	
T-107	IL ROUTE 176	63+61	25.0	R2-1	SPEED LIMIT 30	TELESCOPING	3.00	2.50	7.50	1	7.50		16	1	
T-108	IL ROUTE 176	60+15	-23.5	R2-1	SPEED LIMIT 30	TELESCOPING	3.00	2.50	7.50	1	7.50		16	1	
T-109	IL ROUTE 176	52+41	-48.8	R3-5R	RIGHT TURN ONLY	TELESCOPING	3.00	2.50	7.50	1	7.50		16	1	
T-110	IL ROUTE 176	48+69	-37.2	R2-1	SPEED LIMIT 35	TELESCOPING	3.00	2.50	7.50	1	7.50		16	1	
T-111	IL ROUTE 176	47+18	-40.7	W9-2L	LANE ENDS, MERGE RIGHT	TELESCOPING	3.00	3.00	9.00	1	9.00		16	1	
T-112	IL ROUTE 176	46+29	-46.5	R3-5R	RIGHT TURN ONLY	TELESCOPING	3.00	2.50	7.50	1	7.50		16	1	
T-113	IL ROUTE 176	44+83	-63.4	R1-1	STOP SIGN	TELESCOPING	3.00	3.00	7.45	1	7.45		16	1	
T-114	IL ROUTE 176	44+29	-48.7	R3-5R	RIGHT TURN ONLY	TELESCOPING	3.00	2.50	7.50	1	7.50		16	1	
RELOCATED SIGNS															
T-1A	IL RTE. 176	47+53	24.1	CUSTOM	DOWNTOWN DISTRICT	TELESCOPING	1.50	3.00	4.50	1			14.5	1	
T-1B	IL RTE. 176	47+53	24.1	CUSTOM	RIGHT ARROW	O	1.50	2.00	3.00	1					
T-2A	IL RTE. 176	48+54	22.9	CUSTOM	METRA	TELESCOPING	3.00	2.50	7.50	1			16	1	
T-2B	IL RTE. 176	48+54	22.9	CUSTOM	RIGHT ARROW	O	1.50	2.00	3.00	1					
T-4A	IL RTE. 176	52+15	27.5	CUSTOM	STREET SIGN (THIRD ST)	METAL POST	0.50	2.00	1.00	1					
T-4B	IL RTE. 176	52+15	27.5	CUSTOM	STREET SIGN (TERRA COTTA AVE)	METAL POST	0.50	3.00	1.50	1					
T-6	IL RTE. 176	56+17	59.0	CUSTOM	NO PARKING, THIS SIDE	TELESCOPING	1.50	1.00	1.50	1			14.5	1	
T-8A	IL RTE. 176	56+58	26.4	CUSTOM	STREET SIGN (SECOND ST)	METAL POST	0.50	2.00	1.00	1					
T-8B	IL RTE. 176	56+58	26.4	CUSTOM	STREET SIGN (TERRA COTTA AVE)	METAL POST	0.50	3.00	1.50	1					
T-10A	IL RTE. 176	59+75	32.9	CUSTOM	STREET SIGN (FIRST ST)	MEATAL POST	0.50	2.00	1.00	1					
T-10B	IL RTE. 176	59+75	32.9	CUSTOM	STREET SIGN (TERRA COTTA AVE)	METAL POST	0.50	3.00	1.50	1					
T-21B	IL RTE. 176	44+35	-41.5	CUSTOM	NO PARKING ANY TIME	TELESCOPING	1.50	1.00	1.50	1			14.5	1	
										SUBTOTALS	107.80	0.00	273.50	18.00	0.00
W-102	WALKUP AVENUE	43+43	50.0	R1-1	STOP SIGN	TELESCOPING	3.00	3.00	7.45	1	7.45		16	1	
W-103	WALKUP AVENUE	47+00	53.0	R1-1	STOP SIGN	TELESCOPING	3.00	3.00	7.45	1	7.45		16	1	
W-104	WALKUP AVENUE	47+95	35.0	R3-5fP	RIGHT LANE		1.00	2.50	2.50	1	2.50				
W-105	WALKUP AVENUE	47+95	35.0	R3-6R	THRU/RIGHT TURN	TELESCOPING	3.00	2.50	7.50	1	7.50		16	1	
W-153	WALKUP AVENUE	49+36	-65.5	R1-1	STOP SIGN	TRAFFIC SIGNAL	3.00	3.00	7.45	1	7.45				
W-154	WALKUP AVENUE	48+30	-35.8	R3-5fP	RIGHT LANE		1.00	2.50	2.50	1	2.50				
W-155	WALKUP AVENUE	48+30	-35.8	R3-6R	THRU/RIGHT TURN	TELESCOPING	3.00	2.50	7.50	1	7.50		16	1	
W-156	WALKUP AVENUE	47+30	-34.4	W10-1	RAILROAD GRADE CROSSING ADVANCE WARNING	TELESCOPING	3.00	3.00	7.07	1	7.07		16	1	
W-157	WALKUP AVENUE	46+63	-48.5	R1-1	STOP SIGN	TELESCOPING	3.00	3.00	7.45	1	7.45		16	1	
W-158	WALKUP AVENUE	46+42	-36.5	W9-2L	LANE ENDS MERGE LEFT	TELESCOPING	1.50	1.50	2.25	1	2.25		14.5	1	
SU-102	WALKUP AVENUE	47+23	34.5	R1-2	STOP SIGN	METAL POST	1.50	1.50	2.25	1	2.25				11.50
RELOCATED SIGNS															
W-3A	WALKUP AVENUE	43+58	32.6	CUSTOM	STREET SIGN (RAILROAD ST)	METAL POST	0.75	3.50	2.63	1					
W-3B	WALKUP AVENUE	43+58	32.6	CUSTOM	STREET SIGN (WALKUP AVE)	METAL POST	0.75	3.50	2.63	1					
W-4	WALKUP AVENUE	43+89	23.2	R12-1	WEIGHT LIMIT 12 TONS	TELESCOPING	2.00	1.50	3.00	1			15	1	
W-5A	WALKUP AVENUE	46+74	20.7	R10-7	DO NOT BLOCK INTERSECTION	TELESCOPING	2.50	2.00	5.00	1			15.5	1	
W-5B	WALKUP AVENUE	46+74	20.7	CUSTOM	CRIME STOPPERS	O	1.50	1.00	1.50	1					
W-7A	WALKUP AVENUE	47+59	22.8	CUSTOM	STREET SIGN (GATES ST)	METAL POST	0.75	2.50	1.88	1					
W-7B	WALKUP AVENUE	47+59	22.8	CUSTOM	STREET SIGN (WALKUP AVE)	METAL POST	0.75	3.50	2.63	1					
W-9	WALKUP AVENUE	48+41	24.0	CUSTOM	NO PARKING, ANY TIME	TELESCOPING	1.50	1.00	1.50	1			14.5	1	
W-87A	WALKUP AVENUE	48+21	-21.0	R12-1	WEIGHT LIMIT 12 TONS	TELESCOPING	2.50	2.00	5.00	1			15.5	1	
W-87B	WALKUP AVENUE	48+21	-21.0	CUSTOM	CRIME STOPPERS	O	1.50	1.00	1.50	1				1	
W-90A	WALKUP AVENUE	46+63	-26.4	CUSTOM	STREET SIGN (BURDENT DR)	METAL POST	0.75	3.50	2.63	1					
W-90B	WALKUP AVENUE	46+63	-26.4	CUSTOM	STREET SIGN (WALKUP AVE)	METAL POST	0.75	3.50	2.63	1					
W-92A	WALKUP AVENUE	43+43	-20.5	R8-8	DO NOT STOP ON TRACKS	TELESCOPING	2.50	2.00	5.00	1			15.5	1	
W-92B	WALKUP AVENUE	43+43	-20.5	CUSTOM	WARNING $500 FINE, RAIL ROAD CROSSING	O	2.00	1.50	3.00	1				1	
										SUBTOTALS	61.37	0.00	186.50	14.00	11.50
W-108	WALKUP ROAD	52+33	35.0	R2-1	SPEED LIMIT 30	TELESCOPING	3.00	2.50	7.50	1	7.50		16	1	
W-109	WALKUP ROAD	54+57	35.2	W9-2L	LANE ENDS MERGE LEFT	TELESCOPING	3.00	2.50	7.50	1	7.50		16	1	

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SIGNING SCHEDULE
PROPOSED SIGNS
SHEET 1 OF 3

SCALE: N.T.S. DRAWN BY: MN
DATE: 04/15/11 CHECKED BY: MM

TENG

TENG & ASSOCIATES, INC.
ENGINEERS&ARCHITECTS&PLANNERS
360 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

..\S02A003.DGN..\S02A003.DGN..\B999A00LDGN
4:41:20\ 15/15/15
\\FS-004\AM\VAULT\D-TRANS_07\2202\300-03\CIVIL\CAD\02-CONTRACT\A-TENG\SHEET\S02A002.SHT
STANKIRJ
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63