F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-02-FP	MCHENRY	292	160
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 63522

SCHEDULE OF PROPOSED SIGNS

SIGN ID	ROAD	PROPOSED LOCATION STATION	PROPOSED LOCATION OFFSET (FT) + : RT - : LT	MUTCD CODE	SIGN DESCRIPTION	GROUND MOUNTING TYPE	HEIGHT FT	WIDTH FT	AREA SQ. FT	PANEL TYPE	SIGN PANEL TYPE 1 (SPECIAL)	SIGN PANEL TYPE 2 (SPECIAL)	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)•••	BASE FOR TELESCOPING SIGN SUPPORT (SPECIAL)	METAL POST TYPE A
											X7200105	X7200205	X7280105	X7310110	72900100
W-47	WALKUP ROAD	248+88	-30.3	CUSTOM	RAINTREE DR	TELESCOPING	0.75	2.5	1.875	1			13.75	1	
W-53	WALKUP ROAD	235+78	-29.1	CUSTOM	COACHLIGHT RD	TELESCOPING	0.75	2	1.5	1			13.75	1	
W-59	WALKUP ROAD	228+06	-27.0	CUSTOM	STREET SIGN (ANVIL RD)	TELESCOPING	2	0.75	1.5	1			15	1	
W-60	WALKUP ROAD	228+77	-90.9	R12-1	WEIGHT LIMIT 5 TONS	TELESCOPING	2.5	2	5	1			15.5	1	
W-67A	WALKUP ROAD	74+96	-24.6	CUSTOM	CITY OF CRYSTAL LAKE	TELESCOPING	0.75	2.5	1.875	1			13.75	1	
W-67B	WALKUP ROAD	74+96	-24.6	CUSTOM	OUTSIDE WATER USAGE, CONSERVATION	O	2.5	2.5	6.25	1					
W-69B	WALKUP ROAD	63+59	-71.1	CUSTOM	WARNING NEIGHBORHOOD WATCH	TELESCOPING	1	1.5	1.5	1			14	1	
W-71A	WALKUP ROAD	62+98	-42.2	CUSTOM	STREET SIGN (WALKUP AVE)	LIGHT POLE	0.75	4	3	1					
W-71B	WALKUP ROAD	62+98	-42.2	CUSTOM	STREET SIGN (TALISMON DR)	LIGHT POLE	0.75	4	3	1					
W-73A	WALKUP ROAD	59+90	-34.9	CUSTOM	STREET SIGN (PARKVIEW CT)	METAL POST	0.75	4	3	1					
W-73B	WALKUP ROAD	59+90	-34.9	CUSTOM	STREET SIGN (WALKUP AVE)	METAL POST	0.75	4	3	1					
W-78A	WALKUP ROAD	55+40	-40.8	CUSTOM	STREET SIGN (WALKUP AVE)	METAL POST	0.75	3	2.25	1					
W-78B	WALKUP ROAD	55+40	-40.8	CUSTOM	STREET SIGN (CRYSTAL RIDGE)	METAL POST	0.75	4	3	1					
W-81	WALKUP ROAD	53+25	-43.0	CUSTOM	DOWNTOWN, LEFT ARROW	TELESCOPING	2	2.5	5	1			15	1	
Z-100A	WALKUP ROAD	75+00	23.0	W11-1	BICYCLE	TELESCOPING	2.5	2.5	6.25	1			15.5	1	
Z-100B	WALKUP ROAD	75+00	23.0	W16-9P	AHEAD	O	1	2.5	2.5	1					
Z-101	EXISTING BIKE PATH	76+45	-30.0	R1-1	STOP SIGN	TELESCOPING	1.5	1.5	2.25	1			14.5	1	
Z-102A	WALKUP ROAD	76+47	23.0	W11-1	BICYCLE	TELESCOPING	2.5	2.5	6.25	1			15.5	1	
Z-102B	WALKUP ROAD	76+47	23.0	W16-7PL	DOWN LEFT ARROW	O	1	2.5	2.5	1					
Z-103A	WALKUP ROAD	76+63	-24.0	W11-1	BICYCLE	TELESCOPING	2.5	2.5	6.25	1			15.5	1	
Z-103B	WALKUP ROAD	76+63	-24.0	W16-7PL	DOWN LEFT ARROW	O	1	2.5	2.5	1					
Z-104	EXISTING BIKE PATH	76+65	39.0	R1-1	STOP SIGN	TELESCOPING	1.5	1.5	2.25	1			14.5	1	
Z-105A	WALKUP ROAD	78+22	-24.0	W11-1	BICYCLE	TELESCOPING	2.5	2.5	6.25	1			15.5	1	
Z-105B	WALKUP ROAD	78+22	-24.0	W16-9P	AHEAD	O	1	2.5	2.5	1					
										SUBTOTALS	306.10	20.00	946.75	66.00	23.00
										TOTALS	475.27	20.00	1406.75	98.00	34.50

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SIGNING SCHEDULE
PROPOSED SIGNS
SHEET 3 OF 3

SCALE: N.T.S. DRAWN BY: MN

DATE: 04/15/11 CHECKED BY: MM

TENG

TENG & ASSOCIATES, INC.
ENGINEERS&ARCHITECTS&PLANNERS
360 N MICHIGAN AVE CHICAGO, IL 60601
TELEPHONE: 312616-0000

..\S02IA003.DGN..\S02IA003.DGN..\BD99IA00.DGN STANKIRJ
4:14:20\,15x40) \\FS-0044\AMYVAULT_D-TRANS_OT\2202\300-03\CIVIL\CAD\02_CONTRACT\A-TENG\SHEET\S02IA04.SIT 5659 60 61 62 63
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58