

SUMMARY OF QUANTITIES

SP	SPECIALITY ITEM	CODE NUMBER	ITEM	UNIT	ROADWAY 0003	TRAFFIC SIGNALS 0021	TRAINEES 0042	TOTAL QUANTITY
		54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1			1
		550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	381			381
		550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	212			212
		550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	901			901
		55100500	STORM SEWER REMOVAL 12"	FOOT	171			171
		60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2			2
		60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4			4
		60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	1			1
		60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	7			7
		60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	7			7
*		60255500	MANHOLES TO BE ADJUSTED	EACH	15			15
*		60260100	INLETS TO BE ADJUSTED	EACH	5			5
*		60265700	VALVE VAULTS TO BE ADJUSTED	EACH	4			4
		60500060	REMOVING INLETS	EACH	1			1
		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	443			443
		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2,541			2,541
		66400105	CHAIN LINK FENCE, 4'	FOOT	868			868
		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6			6
		66900200	NON-SPECIAL WASTE DISPOSAL	CY YD	1550			1550
		67100100	MOBILIZATION	L SUM	1			1
		66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1			1
		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12			12
		66900530	SOIL DISPOSAL ANALYSES	EACH	5			5
+		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	17,010			17,010
+		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	141			141
+		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5,951			5,951
		70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,000			2,000
		72000100	SIGN PANEL, TYPE 1	SQ FT	27	40		67
		72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	2			2
		73000100	WOOD SIGN SUPPORT	FOOT	71			71
+		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146			146
+		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,358			7,358
+		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,573			1,573
+		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	448			448
+		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	158			158
+		78100100	REFLECTIVE PAVEMENT MARKER	EACH	8			8
		78200530	BARRIER WALL MARKERS, TYPE C	EACH	160			160
+		78300100	PAVEMENT MARKING REMOVAL	SQ FT	3,023			3,023
*	+	80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH		1		1
+		81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT		604		604
+		81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT		98		98
+		81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT		41		41
+		81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT		64		64

PLAN	DATE
SURVEYED	BY
ALIGNED	
CHECKED	
RT. OF WAY CHECKED	
POD FILE NAME	
NO.	

PROFILE	DATE
SURVEYED	BY
GRADES CHECKED	
B.M. NOTED	
STRUCTURE NOTATIONS OK'D	
NO.	

revised 7-25-11

FILE NAME = 01353887-SHT-500-02.DGN	USER NAME = bherrich	DESIGNED - JC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	VILLAGE OF BURR RIDGE JOLIET RD AT MADISON ST SUMMARY OF QUANTITIES	F.A.U. RTE. 2674	SECTION 06-00034-00-PV	COUNTY DUPAGE	TOTAL SHEETS 69	SHEET NO. 6	
PLOT SCALE = 1/8"=1'	CHECKED - DW	REVISED -	SCALE:			SHEET NO. 2 OF 4 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			
PLOT DATE = 6/22/2011	DATE - 03-28-2011	REVISED -	CONTRACT NO. 63581								