SUMMARY OF QUANTITIES

SP	SPECIALITY TEM	CODE NUMBER	ITEM	UNIT	ROADWAY 0003	TRAFFIC SIGNALS 0021	TRAINEES 0042	TOTAL QUANTITY
		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	34			34
		20200100	EARTH EXCAVATION	CU YD	1,363			1,363
		20800150	TRENCH BACKFILL	CU YD	106			106
		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,644			3,644
		21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	500			500
	+	25000210	SEEDING, CLASS 2A	ACRE	2			2
	+	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	116			116
	+	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	116			116
	+	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	116			116
	+	25100630	EROSION CONTROL BLANKET	SQ YD	6,093			6,093
		25200200	SUPPLEMENTAL WATERING	UNIT	25			25
	+	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150			150
		28000400	PERIMETER EROSION BARRIER	FOOT	1,777			1,777
		28000500	INLET AND PIPE PROTECTION	EACH	2			2
		28000510	INLET FILTERS	EACH	17			17
		31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	349			349
		31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	488			488
		31101810	SUBBASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	2,289			2,289
		35501312	HOT-MIX ASPHALT BASE COURSE, 7"	SQ YD	1,249			1,249
		35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	280			280
		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	700			700
		40600300	AGGREGATE (PRIME COAT)	TON	16			16
		40600525	LEVELING BINDER (HAND METHOD), N50	TON	100			100
		40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	890			890
		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	260			260
		40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	302			302
		40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	36			36
		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	764			764
		42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	488			488
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3,140			3,140
		42400800	DETECTABLE WARNINGS	SQ FT	208			208
		44000100	PAVEMENT REMOVAL	SQ YD	84			84
		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	675			675
		44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	1,152			1,152
		44000600	SIDEWALK REMOVAL	SQ FT	447			447
		44004250	PAVED SHOULDER REMOVAL	SQ YD	459			459
		44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	62			62
		44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	21			21
		44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	15			15
		44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,857			1,857

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / DATA VERIFIED / CADD FILE NAME — NOTE BOOK NO. — BY — DATE

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / DATA VERIFIED / STRUCTURE NOTAT'NS CHK'D — NOTE BOOK NO. — BY — DATE

FILE NAME = D1353887-SHT-SOQ-01.DGN	USER NAME = bhenrich	DESIGNED - JC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	VILLAGE OF BURR RIDGE JOLIET RD AT MADISON ST SUMMARY OF QUANTITIES	F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - BH	REVISED -			2674	06-00034-00-PV	DUPAGE	69	5
	PLOT SCALE = $SCALE$	CHECKED - DW	REVISED -					CONTRACT NO. 63581		
	PLOT DATE = 6/22/2011	DATE - 03-28-2011	REVISED -		SCALE: NTS / SHEET NO. 1 OF 4 SHEETS / STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		