

**SUMMARY OF QUANTITIES**

SP	SPECIALTY TEM	CODE NUMBER	ITEM	UNIT	ROADWAY 0003	TRAFFIC SIGNALS 0021	TRAINEES 0042	TOTAL QUANTITY
	+	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT		430		430
	+	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT		365		365
	+	81400100	HANDHOLE	EACH		8		8
	+	81400200	HEAVY DUTY HANDHOLE	EACH		4		4
	+	81400300	DOUBLE HANDHOLE	EACH		1		1
	+	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT		803		803
	+	84200804	REMOVAL OF POLE FOUNDATION	EACH		1		1
	+	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH		1		1
*	+	86200120	UNINTERRUPTABLE POWER SUPPLY	EACH		1		1
	+	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT		623		623
	+	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT		1,655		1,655
	+	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT		1,608		1,608
	+	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT		1,676		1,676
	+	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT		2,254		2,254
	+	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT		50		50
	+	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH		1		1
	+	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH		3		3
	+	87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH		1		1
	+	87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH		1		1
	+	87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH		1		1
	+	87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH		1		1
	+	87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH		1		1
	+	87800100	CONCRETE FOUNDATION, TYPE A	FOOT		20		20
	+	87800150	CONCRETE FOUNDATION, TYPE C	FOOT		4		4
	+	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT		41		41
*	+	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT		13		13
*	+	88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH		1		1
*	+	88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH		4		4
*	+	88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH		1		1
*	+	88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH		4		4
*	+	88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH		3		3
*	+	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH		2		2
*	+	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH		1		1
	+	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH		8		8
	+	88500100	INDUCTIVE LOOP DETECTOR	EACH		11		11
	+	88600100	DETECTOR LOOP, TYPE I	FOOT		1,208		1,208
*	+	88700200	LIGHT DETECTOR	EACH		3		3
*	+	88700300	LIGHT DETECTOR AMPLIFIER	EACH		1		1
*	+	88800100	PEDESTRIAN PUSH-BUTTON	EACH		4		4
	+	A2C005G5	TREE, ACER SACCHARINUM (SILVER MAPLE), CONTAINER GROWN, 5-GALLON	EACH	5			5

PLAN SURVEYED \_\_\_\_\_ DATE \_\_\_\_\_  
 ALIGNED \_\_\_\_\_  
 CHECKED \_\_\_\_\_  
 NOTE BOOK NO. \_\_\_\_\_  
 FT. OF WAY CHECKED \_\_\_\_\_  
 DDD FILE NAME \_\_\_\_\_

PROFILE SURVEYED \_\_\_\_\_ DATE \_\_\_\_\_  
 GRADES CHECKED \_\_\_\_\_  
 B.M. NOTED \_\_\_\_\_  
 NOTE BOOK NO. \_\_\_\_\_  
 STRUCTURE NOTATIONS CHKD \_\_\_\_\_

FILE NAME = 01353887-SHT-500-03.DGN

USER NAME = bhennrich  
 PLOT SCALE = \*SCALE\*  
 PLOT DATE = 6/22/2011

DESIGNED - JC  
 DRAWN - BH  
 CHECKED - DW  
 DATE - 03-28-2011

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**VILLAGE OF BURR RIDGE JOLIET RD AT MADISON ST  
 SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 3 OF 4 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2674	06-00034-00-PV	DUPAGE	69	7
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
CONTRACT NO. 63581				