

## SCHEDULES OF QUANTITIES

### REMOVAL SCHEDULE

LOCATION	OFFSET		PAVEMENT REMOVAL SQ YD	DRIVEWAY PAVEMENT REMOVAL SQ YD	COMBINATION CURB AND GUTTER REMOVAL FOOT	SIDEWALK REMOVAL SQ FT	PIPE CULVERT REMOVAL FOOT	STORM SEWER REMOVAL 15" FOOT	GUARDRAIL REMOVAL FOOT	REMOVE CONCRETE FLARED END SECTION EACH	RELOCATE EXISTING FLARED END SECTION EACH
	FEET	LT/RT									
<b>S. OLD RAND RD.</b>											
11+00 to 11+92	27	RT		49.2							
12+85 to 13+04	27	RT					20				
12+92	27	RT		20.2							
13+40 to 13+64	29	RT					25				
13+51	27	RT		11.3							
14+07	29	RT								1	
14+30	27	RT		18.0							
14+77	27	RT		10.0							
16+15	27	RT				14					
16+84	27	RT				15					
17+68	27	RT		12.8							
17+90	27	RT		6.8							
18+56	27	RT		11.1							
19+07	27	RT		6.7							
19+65	27	RT		8.3							
20+45	27	RT		12.0							
21+30	27	RT		11.9							
29+09 to 29+73	16	RT	31.0								
29+09 to 29+25	25	RT			16						
29+69	25	RT									1
30+58 to 33+12	15	RT						254			
35+12 to 35+29	20	RT					19				
41+40	23	RT					13			1	
<b>TOTAL</b>			<b>31.0</b>	<b>178</b>	<b>16</b>	<b>29</b>	<b>57</b>	<b>20</b>	<b>254</b>	<b>2</b>	<b>1</b>
<b>SURRYSE RD.</b>											
23+02	35	LT			6						
23+26	35	LT			6						
24+06	39	LT			7						
24+47	39	LT			7						
27+51	35	LT			12						
27+53	42	LT				20					
<b>TOTAL</b>			<b>0.0</b>	<b>0</b>	<b>38</b>	<b>20</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>
<b>TOTAL</b>			<b>31.0</b>	<b>178</b>	<b>54</b>	<b>49</b>	<b>57</b>	<b>20</b>	<b>254</b>	<b>2</b>	<b>1</b>

### DETECTABLE WARNINGS SCHEDULE

LOCATION	OFFSET		DETECTABLE WARNINGS SQ FT
	FEET	LT/RT	
<b>S. OLD RAND RD.</b>			
16+12	27	RT	10
16+52	27	RT	10
22+12	27	RT	10
41+62	19	RT	10
<b>TOTAL</b>			<b>40</b>
<b>SURRYSE RD.</b>			
22+97	35	LT	10
23+25	35	LT	10
24+00	39	LT	10
24+47	39	LT	10
27+51	39	LT	16
<b>TOTAL</b>			<b>56</b>
<b>TOTAL</b>			<b>96</b>

### TREE REMOVAL SCHEDULE

LOCATION	OFFSET RIGHT FEET	TREE REMOVAL (6 TO 15 UNITS DIAMETER)
		UNIT
<b>S. OLD RAND RD.</b>		
Sta. 33+88.96	21.7	6
Sta. 35+27.13	21.2	6
Sta. 35+26.42	24.3	6
Sta. 35+46.83	16.35	8
Sta. 35+64.56	19.7	6
Sta. 35+67.22	19.3	6
Sta. 35+66.73	19.9	6
Sta. 35+71.14	20.3	8
Sta. 36+69.70	20.2	6
Sta. 36+75.11	22.2	6
Sta. 36+98.74	22.5	6
<b>TOTAL</b>		<b>70</b>

### PROPOSED SIDEWALK SCHEDULES

LOCATION	P.C.C. SIDEWALK, 5 INCH (4" SUB-BASE) SQ FT	SUB-BASE GRANULAR MATERIAL, TYPE B 4" SQ YD	P.C.C. SIDEWALK, 6 INCH (6" SUB-BASE) SQ FT	SUB-BASE GRANULAR MATERIAL, TYPE B 6" SQ YD
<b>S. OLD RAND RD.</b>				
10+67 to 11+00	179.0	19.9		
11+00 to 11+92			441	49.0
11+92 to 12+85	473.0	52.6		
12+85 to 13+00			71	7.9
13+00 to 13+43	218.0	24.2		
13+43 to 13+59			80	8.9
13+59 to 14+13	270.0	30.0		
14+13 to 14+46			162	18.0
14+46 to 14+68	111.0	12.3		
14+68 to 14+86			91	10.1
14+86 to 16+17	664.0	73.8		
16+17 to 16+48			SPRUCE ROAD	
16+48 to 17+57	552.0	61.3		
17+57 to 17+80			116	12.9
17+80 to 17+84	20.0	2.2		
17+84 to 17+98			61	6.8
17+98 to 18+45	245.0	27.2		
18+45 to 18+65			100	11.1
18+65 to 19+00	178	19.8		
19+00 to 19+14			60	6.7
19+14 to 19+57	224	24.9		
19+57 to 19+73			75	8.3
19+73 to 20+34	306	34.0		
20+34 to 20+56			108	12.0
20+56 to 21+19	317	35.2		
21+19 to 21+42			107	11.9
21+42 to 22+18	393	43.7		
22+50 to 29+00			WORK OMISSION	
29+06 to 29+86	453	50.3		
29+86 to 33+50	2188	243.1		
33+50 to 33+72	120	13.3		
33+72 to 38+86	2576	286.2		
38+86 to 39+10			111	12.3
39+10 to 41+67	1293	143.7		
<b>TOTAL</b>	<b>10780</b>	<b>1198</b>	<b>1583</b>	<b>176</b>
<b>SURRYSE ROAD</b>				
25+40 to 27+84	1497	166.3		
28+04 to 28+50	305	33.9		
28+70 to 31+20	1566	174.0		
<b>TOTAL</b>	<b>3368</b>	<b>374</b>	<b>0</b>	<b>0</b>
<b>TOTAL</b>	<b>14148</b>	<b>1572</b>	<b>1583</b>	<b>176</b>

### ADDITIONAL PROPOSED ITEMS SCHEDULE

LOCATION	OFFSET		COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 FOOT	THERMOPLASTIC PAVEMENT MARKING-LINE 6" FOOT	SPLIT RAIL FENCE FOOT	RETAINING WALL, SPECIAL SQ FT
	FEET	LT/RT				
<b>S. OLD RAND RD.</b>						
16+18 to 16+48	27	RT		56		
22+18 to 22+47	27	RT		54		
31+25 to 32+75	20	RT			150	
31+25 to 32+75	20	RT				282
41+67 to 42+32	19	RT		115		
29+09 to 33+50	8.5	RT	445			
<b>TOTAL</b>			<b>445</b>	<b>225</b>	<b>150</b>	<b>282</b>
<b>SURRYSE RD.</b>						
24+09 to 24+44	39	LT		74		
<b>TOTAL</b>			<b>0</b>	<b>74</b>	<b>0</b>	<b>0</b>
<b>TOTAL</b>			<b>445</b>	<b>299</b>	<b>150</b>	<b>282</b>

### LANDSCAPING SCHEDULE

LOCATION	TOPSOIL FURNISH AND PLACE, 5"	SEEDING, CLASS 1	MULCH, METHOD 1	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
	SQ YD	ACRE	ACRE	POUND	POUND	POUND
<b>S. OLD RAND RD.</b>						
10+00 to 42+00	584	0.12	0.12	10.86	10.86	10.86
<b>TOTAL</b>	<b>584</b>	<b>0.12</b>	<b>0.12</b>	<b>10.86</b>	<b>10.86</b>	<b>10.86</b>
<b>SURRYSE RD.</b>						
25+40 to 31+20	154	0.03	0.03	2.86	2.86	2.86
<b>TOTAL</b>	<b>154</b>	<b>0.03</b>	<b>0.03</b>	<b>2.86</b>	<b>2.86</b>	<b>2.86</b>
<b>TOTAL</b>	<b>738</b>	<b>0.15</b>	<b>0.15</b>	<b>14</b>	<b>14</b>	<b>14</b>