

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% VP ROADWAY 0004	80% FED 20% VP ARDMORE BRIDGE RECONSTRUCTION SN 022-6930 0014	80% FED 20% VP HILL AVENUE RESURFACING 0005	100% YORK TWP HILL AVENUE RESURFACING 0005	80% FED 20% VP TRAINEES 0042
50102400	CONCRETE REMOVAL	CU YD	209.8		209.8			
50104650	SLOPE WALL REMOVAL	SQ YD	111		111			
50300225	CONCRETE STRUCTURES	CU YD	421.9		421.9			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	214.7		214.7			
50300260	BRIDGE DECK GROOVING	SQ YD	932		932			
50300300	PROTECTIVE COAT	SQ YD	1193		1193			
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	7102		7102			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	75770		75770			
* 50901730	BRIDGE FENCE RAILING	FOOT	228		228			
51100100	SLOPE WALL, 4 INCH	SQ YD	111		111			
51202100	FURNISHING STEEL PILES HP 14X117	FOOT	1474		1474			
51202305	DRIVING PILES	FOOT	924		924			
51204100	TEST PILE STEEL HP 14X17	EACH	2		2			
51500100	NAME PLATES	EACH	1		1			
59000200	EPOXY CRACK INJECTION	FOOT	7		7			
60251730	CATCH BASINS TO BE ADJUST WITH NEW TYPE 23 FRAME AND GRATE	EACH	3	3				
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	1	1				
60255500	MANHOLE TO BE ADJUSTED	EACH	3	3				
6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5			5		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	649	649				
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	644	644				
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4				
63200310	GUARDRAIL REMOVAL	FOOT	644	644				
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	12	12				
67100100	MOBILIZATION	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROECTION, STANDARD 701501	LSUM	1			1		

* SPECIALTY ITEM