

Specialty Item	Special Provision	Item No	Description	Unit	Construction Code 0005 Quantity
	SP	21101605	TOP SOIL FURNISH AND PLACE, 2"	SQ YD	2,600
		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	35
		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	35
		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	35
		25200100	SODDING	SQ YD	2,600
		25200200	SUPPLEMENTAL WATERING	UNIT	40
		28000500	INLET AND PIPE PROTECTION	EACH	60
		28000510	INLET FILTERS	EACH	15
		35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	950
	SP	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	140
		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,900
		40600300	AGGREGATE (PRIME COAT)	TON	20
		40600535	LEVELING BINDER (HAND METHOD), N/0	TON	100
		40600635	LEVELING BINDER (MACHINE METHOD), N/0	TON	1,120
		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	440
		40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	365
		40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N/0	TON	2,200
		40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	40
		42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	400
	SP	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	675
	SP	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	15,900
	SP	42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	3,000
		44000100	PAVEMENT REMOVAL	SQ YD	1,350
		44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	19,000
	SP	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	675
	SP	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	8,500
	SP	44000600	SIDEWALK REMOVAL	SQ FT	18,900
		44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	2,165
		44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	300
		44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	600
		44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	1,000
	SP	44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	19,000
	SP	56500300	DOMESTIC METER VAULTS TO BE ADJUSTED	EACH	3
	SP	56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	7
		60250200	CATCH BASINS TO BE ADJUSTED	EACH	29
		60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	13
		60255500	MANHOLES TO BE ADJUSTED	EACH	1
		60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2
		60260100	INLETS TO BE ADJUSTED	EACH	17
		60265700	VALVE VAULTS TO BE ADJUSTED	EACH	28
		60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	7

Specialty Item	Special Provision	Item No	Description	Unit	Construction Code 0005 Quantity
		60266600	VALVE BOXES TO BE ADJUSTED	EACH	1
		60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	10
		60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	19
	SP	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
		67100100	MOBILIZATION	L SUM	1
		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD, 701501	L SUM	1
		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD, 701701	L SUM	1
		70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD, 701801	L SUM	1
		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,200
		70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150
		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6,500
		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,800
		70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	320
		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	400
		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,500
*		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150
*		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6,500
*		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,800
*		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	320
*		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	400
*	SP	88600600	DETECTOR LOOP REPLACEMENT	FOOT	450
	SP	X0326144	TACTILE/DETECTABLE WARNING SURFACE	SQ FT	1,100
	SP	X0795800	COURSE AGGREGATE	TON	250
	SP	X2020410	EARTH EXCAVATION (SPECIAL)	CY YD	150
	SP	X4400196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	200
	SP	X6022402	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID, SPECIAL	EACH	1
	SP	X6022805	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 1 FRAME, OPEN LID, SPECIAL	EACH	6
	SP	X6022905	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID, SPECIAL	EACH	8
	SP	X6023204	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID, SPECIAL	EACH	13
	SP	X6026628	VALVE BOXES TO BE REPLACED	EACH	1
	SP	X6029600	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID, SPECIAL	EACH	2
	SP	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	18
*	SP	X8140115	HANDHOLE TO BE ADJUSTED	EACH	3
*	SP	X8140215	HEAVY-DUTY HANDHOLE TO BE ADJUSTED	EACH	2
*	SP	Z0001110	GAS VALVE TO BE ADJUSTED	EACH	7
	SP	Z0038116	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 3/4"	SQ YD	1,500
	SP	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CY YD	20
	SP	Z0076600	TRAINERS	FOUR	500
	SP	XX003313	REMOVE AND REINSTALL BRICK PAVEMENT	SQ FT	180
	SP	XX008464	DOMESTIC WATER SERVICE BOX TO BE ADJUSTED (SPECIAL)	EACH	2
	SP	XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	8,500

△ 0042

FILE NAME = FAU 1447 (16TH STREET)- (FROM LOMBARD AVENUE TO CENTRAL AVENUE)	USER NAME =	DESIGNED - AMS	REVISED - AMS 4-7-11
		DRAWN - JFP	REVISED - AMS 4-22-11
	PLOT SCALE =	CHECKED - TPG	REVISED -
	PLOT DATE =	DATE - 3/11	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

**Frank Novotny & Associates, Inc.**  
 835 Midway Drive • Willmetts, IL • 60577 • Telephone: (630) 887-8640 • Fax: (630) 887-0132  
 Civil Engineers  
 Municipal Consultants  
 ILLINOIS PROFESSIONAL DESIGN FIRM NO. 184-000828

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1447	11-00213-00-RS	COOK	25	3
CONTRACT NO. 63607				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT HPP-3045(003)				