

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY 90% FED 10% COUNTY	CONSTRUCTION TYPE CODE	
				0003 QUANTITY	0021 QUANTITY
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	125	125	-
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	111	111	-
* 78300100	PAVEMENT MARKING REMOVAL	50 FT	81	81	-
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	227	227	-
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	-	1
* 81000300	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	43	-	43
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1096	-	1096
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	30	-	30
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	58	-	58
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	10	-	10
* 81018200	CONDUIT PUSHED, 1" DIA., GALVANIZED STEEL	FOOT	87	-	87
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	214	-	214
* 81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	12	-	12
* 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	6	-	6
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	197	-	197
* 81400100	HANDHOLE	EACH	8	-	8
* 81400300	DOUBLE HANDHOLE	EACH	2	-	2
* 81700120	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 6	FOOT	196	-	196
* 81700215	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 2-1/C NO. 10	FOOT	359	-	359
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1237	-	1237
* 82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	2	-	2
+ 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1	-	1
* 86200120	UNINTERRUPTIBLE POWER SUPPLY	EACH	1	-	1
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1	-	1
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1104	-	1104
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	2982	-	2982
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	1541	-	1541
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	798	-	798

+ SPECIAL PROVISION
* SPECIALTY ITEM

FILE NAME: P:\2010\ME\0015_Roselle.D\FCDOT\CADD\Shts\04-S00-sht-Roselle.dgn
PLOT SCALE: 1/8"=1'-0"
USER NAME: Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
630.785.8118 voice, 630.839.2566 fax
www.mps-il.com

MILLENNIA PROFESSIONAL SERVICES

DESIGNED -	CJD	REVISED -	
DRAWN -	CJD	REVISED -	
CHECKED -	TVN	REVISED -	
DATE -	5/23/2011	REVISED -	

**DUPAGE COUNTY
DEPARTMENT OF TRANSPORTATION**

**ROSELLE RD. & WALNUT ST.
INTERSECTION IMPROVEMENTS**

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
364	07-00184-12-CH	DUPAGE	49	5
CONTRACT NO. 63611				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY 90% FED 10% COUNTY	CONSTRUCTION TYPE CODE	
				0003 QUANTITY	0021 QUANTITY
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	1704	-	1704
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4197	-	4197
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	96	-	96
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	534	-	534
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4	-	4
* 87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1	-	1
* 87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1	-	1
* 87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1	-	1
* 87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1	-	1
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16	-	16
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4	-	4
+ 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10	-	10
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	33	-	33
* 87900200	DRILL EXISTING HANDHOLE	EACH	2	-	2
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	5	-	5
* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3	-	3
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	5	-	5
* 88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1	-	1
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8	-	8
* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10	-	10
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	8	-	8
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	479	-	479
* 88700090	CONFIRMATION BEACON	EACH	2	-	2
* 88700200	LIGHT DETECTOR	EACH	2	-	2
+ 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1	-	1
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8	-	8
+ X0320837	EMERGENCY VEHICLE PRIORITY SYSTEM DUEL DETECTOR UNIT	EACH	2	-	2
+ X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	1	1	
+ X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	950	950	-

TOTAL QUANTITY
90% FED
10% COUNTY

CONSTRUCTION TYPE CODE
0003
QUANTITY
0021
QUANTITY

F.A.P. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
364 07-00184-12-CH DUPAGE 49 5
CONTRACT NO. 63611
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT

F:\2010\ME\0015_Roselle.D\FCDOT\CADD\Shts\04-S00-sht-Roselle.dgn