

# SUMMARY OF QUANTITIES

## SUMMARY OF QUANTITIES

100% State 0014 0005 0014 0005 0014 0005

Pay Code	Item	Unit	Total Quantity	Rock Island County				Henry County	
				081-0014 & 081-0015	14 & 15 Approaches	081-0016 & 081-0017	16 & 17 Approaches	037-0025 & 037-0026	25 & 26 Approaches
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	424	56	80	52	80	76	80
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2400		800		800		800
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	846	112	160	102	160	152	160
50157300	PROTECTIVE SHIELD	SQ YD	1000	520		480			
67100100	MOBILIZATION	L SUM	1	0.3		0.4		0.3	
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	3	1		1		1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1					1	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.3		0.4		0.3	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24110	7320		8320		8470	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8040	2440		2775		2825	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3500	1175		1100		1225	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	3500	1175		1100		1225	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3882	1292		1100		1490	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	750	250		250		250	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	6	2		2		2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	6	2		2		2	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE 1)	SQ YD	857	350		257		250	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE 2)	SQ YD	100	100					
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	733	200		250		283	
Z0021907	SILICONE JOINT SEALER 1 3/4 "	FOOT	142	70				72	
Z0021914	SILICONE JOINT SEALER, 2 3/4 "	FOOT	70	70					
Z0021908	SILICONE JOINT SEALER, 2"	FOOT	286			214		72	
Z0041895	POLYMER CONCRETE	CU FT	28.8			20.8		8	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					

\*Specialty Items

Rev. 7-26-11

• (37-1BY-1, 81-1VB, 81-1HB-1)M-1  
•• HENRY & ROCK ISLAND COUNTIES

FILE NAME =	USER NAME = linkdj	DESIGNED -	REVISED -
Q:\BR\CADD plans\Various Counties\2011-1-00 deck patching\PLANeng.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0000' / 1" =		CHECKED -	REVISED -
PLOT DATE = Fri Jun 17 13:03:02 2011		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80			15	3
CONTRACT NO. 64H27				
ILLINOIS FED. AID PROJECT				

SCALE: \_\_\_\_\_ SHEET NO. \_\_\_\_\_ OF \_\_\_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_