PERMANENT AND TEMPORARY PAVEMENT MARKINGS

Location	Length	Urethane Pavement Marking 4" Lt	Urethane Pavement Marking 4" Rt	Preformed Plastic Pavt Marking Ty B, Inlaid 6"	Urethane Pavement Marking 8"	Urethane Pavement Marking Letters & Symbols	Raised Reflective Pavement Markers	Raised Reflective Pavement Markers Removal
	Foot	Foot	Foot	Foot	Foot		Each	Each
SB IL 6								
20+04 TO 56+75	3671	3671	3671	918			46	46
56+75 TO 57+35	60	60	60	15			1	1
Structure 072-0142	105	105	105	27				
58+40 TO 59+00	60	60	60	15			1	1
59+00 TO 91+24	3224	3224	3224	806	862		41	41
91+24 TO 91+84	60	60	60	15	60		1	1
NB IL 6								
19+35 TO 19+65	30	30	30	8			1	1
19+65 TO 56+75	3710	3710	3710	928			47	47
56+75 TO 57+35	60	60	60	15			1	1
Structure 072-0141	105	105	105	27				
58+40 TO 59+00	60	60	60	15			1	1
59+00 TO 96+47	3747	3747	3747	937	862		47	47
96+47 TO 97+07	60	60	60	15	60		1	1
Ramp A								
1+71 TO 7+41	570	570	570		440		60	60
12+69 TO 15+58	289	289	289		72			
15+58 TO 21+42	584	584	584		584	156	15	15
Ramp B								
0+00 TO 7+35	735	735	735					
7+35 TO 21+42	1407	1407	1407					
Ramp C								
0+00 TO 20+35	2035	2035	2035		580		69	69
20+35 TO 23+02	267	267	267		66.75			
23+02 TO 25+89	287	287	287		861	187.2	24	24
Ramp D								
1+56 TO 4+10	254	254	254		254		7	7
4+10 TO 7+18	308	308	308		77			
7+18 TO 33+54	2636	2636	2636					
Total	24324	24324	24324	3739	4779	343.2	362.1	362.1
		48648						

SHORT TERM PAVEMENT MARKING

LOCATION	LENGTH	DASH	SHLDR DIAG	x2 APPS	WORK ZONE MARKING PAVEMENT REMOVAL
	FOOT	FOOT	FOOT	FOOT	SQ FT
SB IL 6					
20+04 TO 56+75	3671	734.2	587.36	2643.12	881.04
56+75 TO 57+35	60	12	9.6	43.2	14.4
Structure 072-0142	105	21	16.8	75.6	25.2
58+40 TO 59+00	60	12	9.6	43.2	14.4
59+00 TO 91+24	3224	644.8	515.84	2321.28	773.76
91+24 TO 91+84	60	12	9.6	43.2	14.4
			Total	5169.6	
NB IL 6					
19+35 TO 19+65	30	6	4.8	21.6	7.2
19+65 TO 56+75	3710	742	593.6	2671.2	890.4
56+75 TO 57+35	60	12	9.6	43.2	14.4
Structure 072-0141	105	21	16.8	75.6	25.2
58+40 TO 59+00	60	12	9.6	43.2	14.4
59+00 TO 96+47	3747	749.4	599.52	2697.84	899.28
96+47 TO 97+07	60	12	9.6	43.2	14.4
			Total	5595.84	
Ramp A					
1+71 TO 7+41	570	228	91.2	638.4	212.8
12+69 TO 15+58	289	115.6	46.24	323.68	107.89
15+58 TO 21+42	584	116.8	93.44	420.48	140.16
Ramp B					
0+00 TO 7+35	735	147	117.6	529.2	176.4
7+35 TO 21+42	1407	281.4	225.12	1013.04	337.68
Ramp C					
0+00 TO 20+35	2035	407	325.6	1465.2	488.4
20+35 TO 23+02	267	160.2	42.72	405.84	135.28
23+02 TO 25+89	287	172.2	45.92	436.24	145.41
Ramp D					
1+56 TO 4+10	254	101.6	40.64	284.48	94.83
4+10 TO 7+18	308	123.2	49.28	344.96	114.99
7+18 TO 33+54	2636	527.2	421.76	1897.92	632.64
			Total	7759.44	
Total	24324	5370.6	3891.84	18524.9	6174.96