

SUMMARY OF QUANTITIES

80/20 NHS FUNDING-0014
PEORIA COUNTY

CODE NO.	ITEM	UNIT	URBAN	TOTAL
42001300	PROTECTIVE COAT	SQYD	46	46
50102400	CONCRETE REMOVAL	CUYD	29.5	29.5
50300255	CONCRETE SUPERSTRUCTURE	CUYD	29.5	29.5
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3043	3043
50800515	BAR SPLICERS	EACH	48	48
52000110	PREFORMED JOINT STRIP SEAL	FOOT	194	194
67100100	MOBILIZATION	LSUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CALMO	2	2
* 70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	5055	5055
* 70300540	PAVEMENT MARKING TAPE, TYPE III, 6"	FOOT	1025	1025
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQFT	1685	1685
70400100	TEMPORARY CONCRETE BARRIER	FOOT	925	925
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	925	925
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	921	921
78300100	PAVEMENT MARKING REMOVAL	SQFT	307	307
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	LSUM	1	1
* X7200201	WIDTH RESTRICTION SIGNING	LSUM	1	1
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	4
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	4
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	LSUM	1	1
* SPECIALTY ITEM				

S:\GEN\DRAW\STD&PLNS\SQUAD BRIDGES\BRIDGE CONTRACTS\JOINTS\68685 SNOT2-0154 US150 ovr CNRR.dgn

FILE NAME = SN072-0154 US150 ovr-UPRR.dgn	USER NAME = jonesco	DESIGNED - C JONES	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES STRUCTURE NO. 072-0154	F.A.P. RTE. 317	SECTION [(16VB)BR]	COUNTY PEORIA	TOTAL SHEETS 14	SHEET NO. 3
PLOT SCALE = 1/32" = 1' / IN.		CHECKED -	REVISED -	SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		Joint Replacements		CONTRACT NO. 68685		
PLOT DATE = 4/27/2011		DATE -	REVISED -			ILLINOIS FED. AID PROJECT				