

SUMMARY OF QUANTITIES

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	*	VAR	38	3
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

\* D4 SCOUR MITIGATION 2011

100% STATE

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE-0014		
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	MCDONOUGH COUNTY	PUTNAM COUNTY	TAZEWELL COUNTY
20300100	CHANNEL EXCAVATION	CU YD	105	53	52	0
25000300	SEEDING CLASS 3	ACRE	1.0	0.2	0.2	0.6
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	18	18	54
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	18	18	54
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	18	18	54
25100630	EROSION CONTROL BLANKET	SQ YD	317	90	90	137
28000400	PERIMETER EROSION BARRIER	FOOT	630	140	100	390
28100209	STONE RIPRAP, CLASS A5	TONS	5050	1945	689	2416
28200200	FILTER FABRIC	SQ YD	2703	997	316	1390
31102000	SUBBASE GRANULAR MATERIAL, TYPE C	CU YD	30	20	10	0
67100100	MOBILIZATION	L SUM	1.0	0.2	0.2	0.6
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.5	0.5	0
X0301852	DEWATERING STRUCTURE NO. 1	EACH	1	1	0	0
X0301853	DEWATERING STRUCTURE NO. 2	EACH	1	0	1	0
X0301854	DEWATERING STRUCTURE NO. 3	EACH	1	0	0	1
X0322587	CONSTRUCTION ACCESS	EACH	3	1	1	1