

COMMITMENTS

No commitments have been made for this project.

GENERAL NOTES

Cleaning & painting of the existing steel shall be as specified in the special provisions for "Cleaning and Painting Existing Steel Structures". All beams, bearings and all other structural steel shall be cleaned per Near White Blast Cleaning-SSPC SP 10 according to the following schedule:

Bridge 1, Structure 072-0147 - Entire Structure.

The designated paint system shall be paint System 1 OZE/U

The final finish coat for the underside shall be Light grey (Munsell No.5B 7/1).

The final finish coat for the fascia beams shall be Interstate Green (Munsell No.7.5G 4/8).

QP1 AND QP2 SHALL BE REQUIRED FOR THIS CONTRACT.

AIR MONITORS - 2 FOR THIS PROJECT.

FILE NAME = 68A51.dgn	USER NAME = AdedeSA	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____	F.A.P. RTE. (318)	SECTION (72-6HB-3)P	COUNTY PEORIA	TOTAL SHEETS 9	SHEET NO. 2
PLOT SCALE = 1:8376' / 1" =	CHECKED - _____	REVISED - _____	CONTRACT NO. 68A51							
PLOT DATE = 5/16/2011	DATE - _____	REVISED - _____	ILLINOIS FED. AID PROJECT							