

# SUMMARY OF QUANTITIES

**URBAN**

			FAP 869( IL 34)	FAP 869( IL 34)	FAP 869( IL 34)
			FUNDING	20% CITY 80% FED	20% STATE 80% FED
			PROJECT TYPE	RESURFACING	RESURFACING
			COUNTY	FRANKLIN	FRANKLIN
			CONSTRUCTION TYPE CODE	CODE 0005	CODE 0005
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	QUANTITY	QUANTITY
Z0034105	MATERIAL TRANSFER DEVICE	TON	3311		3311
Z0048665	<del>RAILROAD PROTECTIVE LIABILITY INSURANCE</del>	L SUM	1		1
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3458	100	3358
40600300	AGGREGATE (PRIME COAT)	TON	58	2	56
40600990	TEMPORARY RAMP	SQ YD	116		116
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N90	TON	3311	47	3264
44000155	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"	SQ YD	38428	557	37871
44201785	CLASS D PATCHES, TYPE I, 12"	SQ YD	6		6
44201789	CLASS D PATCHES, TYPE II, 12"	SQ YD	1412		1412
44201794	CLASS D PATCHES, TYPE III, 12"	SQ YD	436		436
44201796	CLASS D PATCHES, TYPE IV, 12"	SQ YD	618		618
48102100	AGGREGATE <del>WEDGE SHOULDER, TYPE B</del>	TON	137		137
<del>67100100</del>	<del>MOBILIZATION</del>	<del>L SUM</del>	<del>1</del>		<del>1</del>
70100460	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701306</del>	L SUM	1		1
70100600	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701336</del>	L SUM	1		1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2955		2955
70300210	TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	695		695
70300220	TEMPORARY PAVEMENT MARKING, LINE 4"	FOOT	24187		24187
70300280	TEMPORARY PAVEMENT MARKING, LINE 24"	FOOT	120		120
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	492		492
* 78000200	THERMOPLASTIC PAVEMENT MARKING, LINE 4"	FOOT	24187	284	23903
* 78000600	THERMOPLASTIC PAVEMENT MARKING, LINE 12"	FOOT	198		198
* 78000100	THERMOPLASTIC PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ YD	694		694
* 78000400	THERMOPLASTIC PAVEMENT MARKING, LINE 6"	FOOT	288		288
* 78000650	THERMOPLASTIC PAVEMENT MARKING, LINE 24"	FOOT	120		120
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	393		393
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	393		393
88600100	DETECTOR LOOP, TYPE I	FOOT	248		248

\*SPECIALTY ITEM

FILE NAME =	USER NAME = aybar.js	DESIGNED -	DRAWN -	CHECKED -	DATE -	REVISED -	REVISED -	REVISED -	REVISED -	
		<b>STATE OF ILLINOIS</b>		<b>DEPARTMENT OF TRANSPORTATION</b>		SUMMARY OF QUANTITIES				
						SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____				
						F.A.P. RTE. 869	SECTION 10IRS-5	COUNTY FRANKLIN	TOTAL SHEETS 16	SHEET NO. 5
						CONTRACT NO. 78247				
						ILLINOIS FED. AID PROJECT				