

SUMMARY OF QUANTITIES

FAP 821 (IL 15)	FAP 724 (IL 37)	FAP 724 (IL 37)
80% FED.; 20% STATE		80% FED. / 20% CITY
RESURFACING		PARKING LANES
JEFFERSON COUNTY		
CONSTRUCTION TYPE CODE 0005		

URBAN

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY
Z0034105	MATERIAL TRANSFER DEVICE	TON	9151	3841	5272	38
X4420668	CLASS B PATCHES, TYPE IV, 8 INCH (SPECIAL)	SQ YD	28		28	
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1		
Z0048665	PROTECTIVE RAILROAD LIABILITY INSURANCE	L SUM	1	0.5	0.5	
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	11740	4933	6761	46
40600300	AGGREGATE (PRIME COAT)	TON	196	82	113	1
40600855	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N105	TON	3662	1533	2114	15
40600990	TEMPORARY RAMP	SQ YD	508	250	258	
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N105	TON	3181		3158	23
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXTURE E, N105	TON	2308	2308		
44000100	PAVEMENT REMOVAL	SQ YD	28		28	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/2"	SQ YD	65218	27403	37561	254
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	44.1		44.1	
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	15.3		15.3	
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	25		25.0	
44201299	DOWEL BARS 1 1/2"	EACH	44		44	
44201389	CLASS C PATCHES, TYPE II, 13 INCH	SQ YD	850.1	224.0	626.1	
44201394	CLASS C PATCHES, TYPE III, 13 INCH	SQ YD	357.9	120.0	237.9	
44201396	CLASS C PATCHES, TYPE IV, 13 INCH	SQ YD	534.7	53.4	481.3	
44213100	PAVEMENT FABRIC	SQ YD	43.0		43.0	
44213200	SAW CUTS	FOOT	795		795	
44213204	TIE BARS 3/4"	EACH	279		279	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	1	2	
67100100	MOBILIZATION	L SUM	1	0.5	0.5	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	0.5	0.5	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	1	2	

*FAP 821/724 (IL 15/37)

FILE NAME =	USER NAME = mcoor-dkr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et\p\work\p\mcoor-dkr\d0255705\78448-shsta.dgn		DRAWN -	REVISED -		SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____			*	(137.15.1)RS-4	JEFFERSON	37	5
PLOT SCALE = 100.0000' / 1"		CHECKED -	REVISED -									
PLOT DATE = 5/12/2011		DATE -	REVISED -									
CONTRACT NO. 78248												
ILLINOIS FED. AID PROJECT												