

**FAP 821 ( IL 15) PAVEMENT RESURFACING SCHEDULE**

LOCATION STATION TO STATION	LENGTH <small>FOR INFORMATIONAL PURPOSE ONLY</small> ( FT )	ROADWAY WIDTH ( FT )	ROADWAY AREA ( SQ YD )	HOT-MIX ASP. SURF. REMOV. 2 1/2" ( SQ YD )	TEMP RAMP ( SQ YD )	POLY. HOT-MIX ASP. SUR. CSE. MIX E, N 105 ( 1 1/2" ) ( TON )	POLY. LEVELING BINDER ( MM ) N90 ( 1" ) ( TON )	POLY. BIT. MAT. ( PRIME COAT ) ( GAL )	AGG. ( PRIME COAT ) ( TON )	NOTES									
											( FT )	( FT )	( SQ YD )	( SQ YD )	( SQ YD )	( TON )	( TON )	( GAL )	( TON )
											<b>FAP 821 ( IL 15 - Broadway Ave. ) - STA. 612+60 to STA. 623+90</b>								
612+60.00 TO 623+90.00	1130	54	6780	6780	51	570	379	1220	20										
623+90.00 TO 626+00.00	210	57	1330	1330		112	75	239	4										
626+00.00 TO 651+32.46	2532	60	16883	16883		1419	942	3039	51										
651+32.46 TO 652+45.00	113	33	413	413		35	23	74	1										
Lt. 651+32.46 TO 652+45.00	113	5	63	63		6	4	11	0	Painted Median Area									
652+45.00 TO 654+21.00	176	41	802	802	40	68	45	144	2										
<b>Ex. Railroad Crossing - Sta. 654+21 to Sta. 654+42</b>																			
654+42.00 TO 655+00.00	58	46	296	296	84	25	17	53	1										
<b>FAP 821 ( IL 15 -Main St. ) - STA. 29+56.55 to STA. 32+60</b>																			
<b>Eq. Sta. 651+32.46 ( bk. ) = Sta. 29+56.55 ( ah. )</b>																			
29+56.55 TO 30+69.00	112	28.0	350	350		30	20	63	1										
30+69.00 TO 31+55.72	87	26.0	251	251		22	14	45	1										
<b>Eq. Sta. 31+55.72 ( bk. ) = Sta. 31+56.77 ( ah. )</b>																			
31+56.77 TO 31+58.00	1	26.0	4	4	25	1	1	1	0										
<b>Ex. Railroad Crossing - Sta. 31+58 to Sta. 31+80</b>																			
31+80.00 TO 32+60.00	80	26.0	231	231	50	20	13	42	1										
<b>FAP 821 ( IL 15) TOTALS</b>				<b>27,403</b>	<b>250</b>	<b>2308</b>	<b>1533</b>	<b>4933</b>	<b>82</b>										

\*FAP 821/724 ( IL 15/37)

FILE NAME =	USER NAME = mcoordkr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 15 RESURFACING SCHEDULE</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pr_work\pwork\mcoordkr\d0255706\7848-ahts.dgn	DRAWN -	REVISED -	REVISED -		SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	137.15.DRS-4	JEFFERSON	37	15	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	REVISED -							CONTRACT NO. 7824B		
PLOT DATE = 5/11/2011	DATE -	REVISED -	REVISED -							ILLINOIS FED. AID PROJECT		