

SUMMARY OF QUANTITIES

RURAL - POPE COUNTY					
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	100% STATE CONSTRUCTION TYPE CODE	
				0040	0040
				LOCATION 1	LOCATION 2
QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
20200100	EARTH EXCAVATION	CU YD	37	16	21
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	44	19	25
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	694	347	347
40600990	TEMPORARY RAMP	SQ YD	116	58	58
40603320	HOT- MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	94	41	53
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	439	193	246
40600300	AGGREGATE (PRIME COAT)	TON	14	6	8
44000100	PAVEMENT REMOVAL	SQ YD	78		78
44004250	PAVED SHOULDER REMOVAL	SQ YD	189		189
44200966	CLASS B PATCHES, TYPE 1, 10 INCH	SQ YD	4.5		4.5
44213100	PAVEMENT FABRIC	SQ YD	4.5		4.5
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	125	74	51
48203100	HOT-MIX ASPHALT SHOULDERS	TON	18		18
50102400	CONCRETE REMOVAL	CU YD	1		1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1		1
63301000	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL	FOOT	135		135
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	1.5	1.5
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1		1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1		1
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1416	631	785
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	2	2
X0326767	PROFILE DIAMOND GRINDING CONCRETE PAVEMENT	SQ YD	214	107	107
Z0010614	CLEANING EXISTING MANHOLE OR HANDHOLE	EACH	1		1
Z0064300	SEALING CRACKS	FOOT	264	132	132