

SUMMARY OF QUANTITIES

ITEM NO.	SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
						0001	0021	0008
						ROADWAY	LIGHTING	STRUCTURE
1		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1162	1162		
2		20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1358	1358		
3	SI	20101400	NITROGEN FERTILIZER NUTRIENT	POUND	232	232		
4	SI	20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	232	232		
5	SI	20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	232	232		
6		20200100	EARTH EXCAVATION	CU YD	15629	15629		
7	SP	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1000	1000		
8	SP	20400800	FURNISHED EXCAVATION	CU YD	1942	1942		
9		20800150	TRENCH BACKFILL	CU YD	525	525		
10		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	12949	12949		
11	SI	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	18698	18698		
12	BDE, SI	25100115	MULCH, METHOD 2	ACRE	2.1	2.1		
13	SI	25200100	SODDING	SQ YD	18698	18698		
14	SI	25200200	SUPPLEMENTAL WATERING	UNIT	225	225		
15	SI	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	847	847		
16	BDE	28000305	TEMPORARY DITCH CHECKS	FOOT	336	336		
17	SI	28000400	PERIMETER EROSION BARRIER	FOOT	2150	2150		
18		28000500	INLET AND PIPE PROTECTION	EACH	13	13		
19		28100107	STONE RIPRAP, CLASS A4	SQ YD	980	64		916
20		28200200	FILTER FABRIC	SQ YD	1008	92		916
21		31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	6350	6350		
22		35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1968	1968		
23		35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	800	800		
24		35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	394	394		
25	SP	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	418	418		
26		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8049	8049		
27		40600300	AGGREGATE (PRIME COAT)	TON	25	25		
28		40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	141	141		
29		40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
30		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	356	356		
31		40600990	TEMPORARY RAMP	SQ YD	23	23		
32		40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	6827	6827		
33		40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2212	2212		
34		40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	107	107		
35		42001300	PROTECTIVE COAT	SQ YD	2159	2159		
36		42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	768	768		
37		42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	398	398		
38		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6829	6829		
39		42400800	DETECTABLE WARNINGS	SQ FT	26	26		
40		44000100	PAVEMENT REMOVAL	SQ YD	6518	6518		

ITEM NO.	SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
						0001	0021	0008
						ROADWAY	LIGHTING	STRUCTURE
41		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1335	1335		
42		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	270	270		
43		44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	58	58		
44		44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	32	32		
45		48101200	AGGREGATE SHOULDERS, TYPE B	TON	289	289		
46		50105220	PIPE CULVERT REMOVAL	FOOT	228	228		
47		50200100	STRUCTURE EXCAVATION	CU YD	245			245
48		50200300	COFFERDAM EXCAVATION	CU YD	355			355
49		50202901	COFFERDAM (LOCATION - I)	EACH	1			1
50		50300225	CONCRETE STRUCTURES	CU YD	588.5			588.5
51		50300255	CONCRETE SUPERSTRUCTURE	CU YD	1061.1			1061.1
52		50300260	BRIDGE DECK GROOVING	SQ YD	2361			2361
53		50300280	CONCRETE ENCASEMENT	CU YD	135.6			135.6
54	SP	50300285	FORM LINER TEXTURED SURFACE	SQ FT	12135			12135
55		50300300	PROTECTIVE COAT	SQ YD	3990			3990
56		50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1
57		50500505	STUD SHEAR CONNECTORS	EACH	10947			10947
58	BDE	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	331540			331540
59		50800515	BAR SPLICERS	EACH	106			106
60	SI	50901720	BICYCLE RAILING	FOOT	787	108		679
61	SI	50901750	PARAPET RAILING	FOOT	1237			1237
62		51201610	FURNISHING STEEL PILES HP12x63	FOOT	502			502
63		51201710	FURNISHING STEEL PILES HP12x84	FOOT	779			779
64		51201900	FURNISHING STEEL PILES HP14x89	FOOT	320			320
65		51202000	FURNISHING STEEL PILES HP14x102	FOOT	517			517
66		51202305	DRIVING PILES	FOOT	502			502
67		51203610	TEST PILE STEEL HP12x63	EACH	2			2
68		51500100	NAME PLATES	EACH	1			1
69		52000110	PREFORMED JOINT STRIP SEAL	FOOT	62			62
70		52000220	FINGER PLATE EXPANSION JOINT, 6"	FOOT	47			47
71		52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	46			46
72		52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	8			8
73		52100030	ELASTOMERIC BEARING ASSEMBLY, TYPE III	EACH	6			6
74		52100540	ANCHOR BOLTS, 1 1/2"	EACH	84			84
75		542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	114	114		
76		542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	28	28		
77		542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	14	14		
78	BDE, SP	542C012	PIPE CULVERTS, CLASS C, TYPE 1 12" (TEMPORARY)	FOOT	105	105		
79		54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3	3		
80		54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1		

SP=SPECIAL PROVISION SI=SPECIALITY ITEM BDE=BUREAU OF DESIGN AND ENVIRONMENT GBSP=GUIDE BRIDGE SPECIAL PROVISION

FILE NAME = V:\2545\2545q001.dgn	USER NAME = bdeoraene	DESIGNED - DRAWN -	REVISED - REVISED -
	PLOT SCALE = 1/800' / IN.	CHECKED -	REVISED -
	PLOT DATE = 5/25/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

T.R. 55 (RENWICK RD.) SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 3 SHEETS STA. N/A TO STA. N/A

F.A. RTE. TR 55	SECTION 90-16103-01-BR	COUNTY WILL	TOTAL SHEETS 255	SHEET NO. 3
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 83126	