

SUMMARY OF QUANTITIES

ITEM NO.	SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
						0001	0021	0008
						ROADWAY	LIGHTING	STRUCTURE
81		54213867	STEEL END SECTIONS 12"	EACH	3	3		
82		54213873	STEEL END SECTIONS 18"	EACH	2	2		
83		550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	244	244		
84		550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	270	270		
85		550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	144	144		
86		550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1096	1096		
87		550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	258	258		
88		550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	756	756		
89		550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	636	636		
90		550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	108	108		
91		550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	228	228		
92	SI	56400100	FIRE HYDRANTS TO BE MOVED	EACH	3	3		
93	SP, SI	56400510	FIRE HYDRANTS TO BE REMOVED AND REPLACED	EACH	2	2		
94	SP, SI	56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	2	2		
95		58700300	CONCRETE SEALER	SQ FT	440			440
96		59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	91			91
97		60100945	PIPE DRAINS 12"	FOOT	44	44		
98		60107600	PIPE UNDERDRAINS 4"	FOOT	551	551		
99		60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	11	11		
100		60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	3	3		
101		60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2		
102		60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5		
103		60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2	2		
104		60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	3	3		
105		60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	18	18		
106		60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	4	4		
107		60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	22	22		
108		60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	4	4		
109		60255500	MANHOLES TO BE ADJUSTED	EACH	7	7		
110		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	269	269		
111		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	6296	6296		
112		60900515	CONCRETE THRUST BLOCKS	EACH	1	1		
113	SP	63200310	GUARDRAIL REMOVAL	FOOT	589	589		
114		66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	23	23		
115	BDE	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24		
116		67100100	MOBILIZATION	L SUM	1	0.5		0.5
117	SI	67201000	SEALING ABANDONED WATER WELLS	EACH	5	5		
118	BDE	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	100	100		
119	SP	70104490	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 1	L SUM	1	1		
120	SP	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2		

ITEM NO.	SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
						0001	0021	0008
						ROADWAY	LIGHTING	STRUCTURE
121	SI	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4027	4027		
122	SI	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1017	1017		
123	SI	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	43625	43625		
124	SI	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	586	586		
125	SI	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	154	154		
126	SI	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	583	583		
127	SI	70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	73	73		
128	SI	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	641	641		
129	SI	70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	601	601		
130	SI	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	11148	11148		
131		70400100	TEMPORARY CONCRETE BARRIER	FOOT	287.5	287.5		
132	SI	72000100	SIGN PANEL - TYPE 1	SQ FT	22	22		
133	SI	72000200	SIGN PANEL - TYPE 2	SQ FT	20	20		
134	SI	72500100	OBJECT MARKER - TYPE 1	EACH	4	4		
135	SI	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	68	68		
136	SI	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	609	609		
137	SI	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9527	9527		
138	SI	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	560	560		
139	SI	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	122	122		
140	SI	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	198	198		
141	SI	78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	63	63		
142	SI	78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	2064	2064		
143	SI	78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	26	26		
144	SI	78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	35	35		
145	SI	78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	56	56		
146	SP, SI	80400100	ELECTRIC SERVICE INSTALLATION	EACH	2			2
147	SP, SI	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1			1
148	SI	81000700	CONDUIT IN TRENCH, 2-1/2" DIA., GALVANIZED STEEL	FOOT	115			115
149	SI	81021370	CONDUIT PUSHED, 4" DIA., PVC	FOOT	488			488
150	SI	81702460	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 3/0	FOOT	200			200
151	SP, SI	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	150			150
152	SP, SI	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4			4
153	SI	83050760	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 8 FT. MAST ARM	EACH	4			4
154	SI	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	250			250
155	SI	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	4			4
156	SI	A2001716	TREE, ACER SACCHARUM (SUGAR MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	5			5
157	SI	A2002016	TREE, AESCULUS GLABRA (OHIO BUCKEYE), 2" CALIPER, BALLED AND BURLAPPED	EACH	3			3
158	SI	A2002516	TREE, CARPINUS CAROLINIANA (AMERICAN HORNBEAM), 2" CALIPER, BALLED AND BURLAPPED	EACH	5			5
159	SI	A2002616	TREE, CARYA CORDIFORMIS (BITTERNUT HICKORY), 2" CALIPER, BALLED AND BURLAPPED	EACH	10			10
160	SP, SI	A2002716	TREE, CARYA OVATA (SHAGBARK HICKORY), 2" CALIPER, BALLED AND BURLAPPED	EACH	20			20

SP=SPECIAL PROVISION SI=SPECIALITY ITEM BDE=BUREAU OF DESIGN AND ENVIRONMENT GBSP=GUIDE BRIDGE SPECIAL PROVISION

FILE NAME = V:\2545\2545q002.dgn	USER NAME = bdecrane	DESIGNED - DRAWN -	REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>T.R. 55 (RENWICK RD.) SUMMARY OF QUANTITIES</b>				F.A. RTE. TR 55	SECTION 90-16103-01-BR	COUNTY WILL	TOTAL SHEETS 255	SHEET NO. 4
	PLOT SCALE = 1:800' / 1" IN.	CHECKED -	REVISED -		SCALE: N/A	SHEET NO. 2 OF 3 SHEETS	STA. N/A	TO STA. N/A	CONTRACT NO. 83126				
	PLOT DATE = 5/25/2011	DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								