

TEMPORARY PAVEMENT MARKING (for temporary pavement / staging)																
STATION	TO	STATION	LETTERS & SYMBOLS		LINES				PAVEMENT MARKING TAPE, TYPE III						LETTERS & SYMBOLS	
			TURN ARROW	"ONLY"	4"		24"		4"		6"		6"		WHITE ARROW / ONLY	BLACK COVER UP
					SOLID WHITE LANE LINE	DOTTED WHITE LANE TAPER	SOLID WHITE EDGE LINE	DBL YELLOW CENTER LINE	SOLID WHITE STOP BAR	SOLID WHITE EDGE LINE	WHITE LANE LINE	DOTTED WHITE LANE TAPER	YELLOW CL	BLACK COVER UP		
SQ FT			FOOT				FOOT						SQ FT			
T.R. 55 (RENWICK RD.)																
STAGE 1B																
127+65.5	TO	135+55.3					1606.9	1606.0	10.0							
STAGE 1C																
101+30.0	TO	104+79.0								350.0	20.0	28.0	243.0	601.0	36.3	36.4
102+69.0	TO	112+51.5					1377.8	1909.2								
STAGE 1D																
127+36.0	TO	135+62.0					1102.7	1654.0	19.6							
STAGE 2																
105+36.0	TO	126+44.3	15.6	20.8	117.0	6.0		3033.4	35.0							
127+36.3	TO	133+44.2	15.6	20.8	117.0	32.0		2121.2	36.0							
RIVER RD.																
STAGE 1A																
12+94.2	TO	12+94.2							12.0							
13+81.2	TO	13+81.2							10.0							
STAGE 1B																
8+36.0	TO	12+78.6					887.5	884.4	10.0							
13+58.4	TO	18+36.7					925.4	955.2	10.0							
STAGE 1C																
7+73.4	TO	12+63.0					528.4	979.4	10.0							
13+75.1	TO	19+81.0					760.8	1218.0	10.0							
STAGE 1D																
12+63.1	TO	13+40.1					77.1	154.2	10.0							
13+75.1	TO	19+81.0					274.7	548.4	10.0							
STAGE 2																
8+19.8	TO	12+97.1					887.5	929.2	19.5							
13+95.1	TO	17+64.1					264.7	738.4	10.0							
STAGE 3																
7+91.3	TO	12+97.1					505.6	1011.8	10.0							
13+95.1	TO	17+64.1					264.7	528.4	20.0							
POST STAGE 3																
7+91.3	TO	19+81.0	31.2	241.6	230.0	64.0	120.0	3469.6	66.2							
OLD RENWICK RD.																
STAGE 2																
49+09.0	TO	49+81.0						143.6	20.3							
TOTAL			62.4	283.2	464.0	102.0	9583.8	21884.4	328.6	350.0	20.0	28.0	243.0	601.0	36.3	36.4
USE			346			32035		329		641			601		73	

NOTE 1: THE TYPE III PAVEMENT MARKING TAPE IS TO BE USED TO PRESERVE THE EXISTING MARKINGS AND PAVEMENT SURFACE.
NOTE 2: SEE FINAL PAVEMENT MARKING PLANS FOR STAGE 2 MARKINGS ON THE BRIDGE.

FENCE AND GATE REMOVAL						
STATION	TO	STATION	SIDE	CHAIN LINK FENCE REMOVAL FOOT	WOODEN FENCE REMOVAL FOOT	GATE REMOVAL EACH
T.R. 55 (RENWICK RD.)						
129+85.0	TO	130+10.0	RT			1.0
130+22.0	TO	130+22.0	RT	11.0		
130+22.0	TO	131+40.0	RT		118.0	
131+90.3	TO	132+06.3	RT		16.0	
RIVER RD.						
10+15.8	TO	10+15.8	RT	15.0		
11+98.0	TO	12+24.0	RT			1.0
TOTAL				26.0	134.0	2.0
USE				26	134	2

BUILDING REMOVAL						
STATION +/-	SIDE	OFFSET +/- FEET	TYPE	BUILDING REMOVAL NO.	L	SUM
T.R. 55 (RENWICK RD.)						
123+11.0	RT	52	HOUSE	4	1	
123+76.0	LT	24	HOUSE	2	1	
123+85.0	RT	23	GARAGE	5	1	
124+33.0	LT	85	GARAGE	3	1	
125+70.0	RT	26	HOUSE	6	1	
OLD RENWICK RD.						
43+76.0	RT	275	SHED	8	1	
44+03.0	LT	81	HOUSE	1	1	
44+44.0	RT	88	HOUSE	7	1	
SEE SPECIAL PROVISIONS.						

THERMOPLASTIC PAVEMENT MARKING											
STATION	TO	STATION	LETTERS AND SYMBOLS			LINES					
			RAILROAD CROSSING	ONLY	TURN ARROW	4"		6"		12"	24"
						SOLID WHITE	DOUBLE YELLOW	SOLID WHITE	DOTTED WHITE	SOLID YELLOW	SOLID WHITE
SQ FT			EDGE OF PAV'T.		CL & MEDIAN	LANE LINE	LANE LINE	MED./DIAG.	LINE		
T.R. 55 (RENWICK RD.)											
104+55.4	TO	RAILROAD	62.6				2849.8		10.4	84.0	
RAILROAD	TO	BRIDGE				168.0				28.0	
*(SEE EPOXY PAVEMENT MARKING SCHEDULE FOR BRIDGE AREAS).											
BRIDGE	TO	RIVER RD.	120.8	15.6		209.4	115.0	6.0			
RIVER RD.	TO	133+44.2	120.8	15.6		235.5	2115.8	115.0	30.0	44.3	
OLD RENWICK RD.											
48+20.0	TO	49+79.0					358.0			19.0	
RIVER RD.											
7+91.0	TO	T.R. 55 (RENWICK RD.)	120.8	15.6		1692.2	115.0	32.0	34.0	33.2	
T.R. 55 (RENWICK RD.)	TO	19+81.3	120.8	15.6		120.0	1777.4	115.0	32.0	32.4	
TOTAL			62.6	483.2	62.4	355.5	9170.6	460.0	100.0	121.1	197.3
USE			609			9527		560		122	198

EPOXY PAVEMENT MARKING										
STATION	TO	STATION	LETTERS & SYMBOLS		LINES					
			RAILROAD CROSSING	SQ FT	4"		6"		12"	24"
					DOUBLE YELLOW	CL & MEDIAN	DOTTED WHITE	SOLID WHITE	SOLID YELLOW	SOLID WHITE
FOOT			FOOT							
T.R. 55 (RENWICK RD.) - ON BRIDGE										
118+20.5	TO	125+03.7	62.6		2063.2	26.0	34.5	56.0		
TOTAL			62.6		2063.2	26.0	34.5	56.0		
USE			63		2064	26	35	56		