

SIGN SCHEDULE

LOCATION	STANDARD NUMBER (NEW) DESCRIPTION (EXISTING)	SIGN PANEL TYPE 1 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY TYPE A (EACH)	RELOCATE SIGN PANEL ASSEMBLY TYPE A (EACH)	RELOCATE SIGN PANEL TYPE 1 (SQ FT)	METAL POST, TYPE B (FOOT)	SIGN PLACEMENT HEIGHT ABOVE EDGE OF PAVEMENT	CENTERLINE OFFSET
LASALLE STREET								
STA. 112+64.0 RT	STOP SIGN				4		9'-0"	13'
STA. 112+64.0 RT	R3-2-2424	4.00				15.5	7'-0"	13'
STA. 113+43.0 RT	S1-1-3636	9.00					9'-0"	14'
STA. 113+43.0 RT	W16-7P-2412	2.00				15.0	7'-0"	14'
STA. 113+49.5 LT	S1-1-3636	9.00					8'-0"	13'
STA. 113+49.5 LT	W16-7P-2412	2.00				15.0	7'-0"	13'
STA. 113+59.1 LT	STOP SIGN*						7'-0"	25.2'
STA. 113+98 LT	DO NOT ENTER**				4		7'-0"	25'
STA. 113+98 LT	R1-1-3030	6.25				13.5	7'-0"	25'
STA. 113+98 LT	S1-1-3636	9.00					8'-0"	14'
STA. 113+98 LT	W16-7P-2412	2.00				15.0	7'-0"	25'
STA. 114+18 LT	R1-1-3030	6.25				13.5	7'-0"	13'
STA. 117+94 LT	STOP SIGN		1			13.5	7'-0"	34'
STA. 122+22 LT	STOP SIGN		1				7'-0"	42.5'
STA. 122+22 LT	STREET NAME SIGN					15.5	9'-6"	42.5'
STA. 126+42 LT	STOP SIGN			1			7'-0"	39'
STA. 126+42 LT	STREET NAME SIGN					15.5	9'-6"	39'
STA. 130+98 LT	STOP SIGN			1			7'-0"	39'
STA. 130+98 LT	STREET NAME SIGN					15.5	9'-6"	39'
STA. 139+93 LT	STOP SIGN					13.5	7'-0"	39'
STA. 146+61 RT	STOP SIGN		1			13.5	7'-0"	15.6'
STA. 147+48 LT	STOP SIGN		1			13.5	7'-0"	13.2'
STA. 149+85 RT	R1-1-3030	6.25				13.5	7'-0"	12.5'
STA. 150+70 LT	R1-1-3030	6.25				13.5	7'-0"	12.5'
SUBTOTAL LASALLE STREET		62.00	2	4	8.00	215.00		
WASHINGTON STREET								
STA. 200+47 LT	STOP SIGN			1		15.5	7'-0"	40'
STA. 204+80 LT	STREET NAME SIGN						9'-6"	42'
STA. 204+80 LT	STOP SIGN			1		13.5	7'-0"	42'
SUBTOTAL WASHINGTON STREET		0.00		2		29.00		
ROUTE 34 AT GREEN STREET								
	S1-1-3636 W16-7P-2412***	22.00				30.0	7'-0"	VARIES
EAST OF GREEN STREET	S1-1-3636-3636 W16-9P-2412*	11.00					7'-0"	VARIES
WEST OF GREEN STREET	S1-1-3636 W16-9P-2412	11.00				16.0	7'-0"	VARIES
BELOW 35 MPH SPEED LIMIT SIGN	S5-2-2430	5.00						
SUBTOTAL ROUTE 34 AT GREEN STREET		49.00				46.0		
ROUTE 34 AT GAGE STREET								
	S1-1-3636 W16-7P-2412	13.00				15.0	7'-0"	VARIES
BELOW 35 MPH SPEED LIMIT SIGN	S5-2-2430	5.00						
SUBTOTAL ROUTE 34 AT GAGE STREET		18.00				15.0		
TOTAL		129.00	2	6	8	305		

*ATTACHED TO POWER POLE
 **ON BACK OF STOP SIGN. SCHOOL CROSSING ASSEMBLY AND STOP SIGN ON TWO SEPARATE POSTS.
 *** ONE SIGN PER LEG OR TWO PER CROSSWALK FOR A TOTAL OF 2 SIGN ASSEMBLIES AND 2 POSTS.

PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKING			PAVEMENT MARKING REMOVAL (SQ FT)	
	LINE - 6" CROSSWALK SOLID WHITE (FOOT)	LINE - 12" CROSSWALK SOLID WHITE (FOOT)	LINE - 24" STOP BAR WHITE (FOOT)		
LASALLE STREET					
STA. 109+11.6 TO STA. 109+48.5 LT	69				
STA. 113+07.3 TO STA. 113+20.0 LT/RT				44	
STA. 113+43.7 TO STA. 113+43.7 LT/RT	47	54			
STA. 113+51.8 TO STA. 114+08.2 LT	95	110	32		
STA. 114+18 TO STA. 114+18 LT			11		
STA. 117+91.3 TO STA. 118+20.3 LT	51		11		
STA. 122+22.8 TO STA. 122+47.5 LT	46		10		
STA. 126+22.7 TO STA. 126+22.7 RT			13		
STA. 126+28.7 TO STA. 126+28.7 LT/RT	51				
STA. 126+43.4 TO STA. 126+78.2 LT	67		18		
STA. 130+77.7 TO STA. 131+05.9 LT	52		11		
STA. 139+93.4 TO STA. 140+12.0 LT	37		9		
STA. 146+76.4 TO STA. 147+33.0 LT	100		19		
STA. 149+85.0 TO STA. 149+85.0 RT			10		
STA. 150+04.6 TO STA. 150+46.9 LT	75		14		
STA. 150+70.0 TO STA. 150+70.0 LT			10		
SUBTOTAL LASALLE STREET		690	164	168	44
WASHINGTON STREET					
STA. 200+45.7 TO STA. 200+77.1 LT	55		13		
STA. 204+79.2 TO STA. 205+04.6 LT	47		11		
SUBTOTAL WASHINGTON STREET		102		24	
ROUTE 34 AT GREEN STREET					
	246	117	30		
ROUTE 34 AT GAGE STREET					
	213	90	30		
TOTAL		1251	371	252	44

DRAINAGE SCHEDULE

LOCATION	STORM SEWER CLASS B TYPE 1 6" (FT)	INLETS TYPE A TYPE B GRATE (EACH)	MANHOLES TO BE ADJ W/ NEW TYPE 1 FRAME AND OPEN LID (EACH)
LASALLE STREET			
STA. 111+16.69, 23.6' LT			1
STA. 113+50.00, 35.5' LT			1
STA. 114+24.73, 11.6' LT			1
STA. 118+24.45, 35.6' LT			1
STA. 121+06, 21.3' LT TO 33.3' LT	12		
STA. 122+50.42, 37.4' LT	7	1	
STA. 122+50.3, 28.4' LT			1
TOTAL		1	5

DATE: _____
 BY: _____
 SURVEYED: _____
 PLOTTED: _____
 CHECKED: _____
 PLAN NO.: _____
 NOTE BOOK NO.: _____
 CAD FILE NAME: _____

DATE: _____
 BY: _____
 SURVEYED: _____
 PLOTTED: _____
 CHECKED: _____
 PROFILE NO.: _____
 NOTE BOOK NO.: _____
 STRUCTURE NOTATIONS: CPKD



USER NAME = JR:rbu
 DESIGNED -
 DRAWN -
 CHECKED -
 DATE -
 REVISED -
 REVISED -
 REVISED -
 REVISED -

VILLAGE OF SOMONAUK

SCHEDULE OF QUANTITIES

SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____

C.H. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00021-00-SW	LASALLE	18	5
CONTRACT # 87455				
FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				