

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION CODE	UNIT	0031		
				TOTAL QUANTITY	100% LOCAL (US DOT TIGER) QTY	80% ITEP 20% LOCAL QTY
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)		UNIT	6	6	
* 20101000	TEMPORARY FENCE		FOOT	1000	1000	
20200100	EARTH EXCAVATION		CU YD	1400	1400	
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL		CU YD	140	140	
* 21000300	GRANULAR EMBANKMENT, SPECIAL		TON	287	287	
△ 25200110	SODDING, SALT TOLERANT		SQ YD	426	426	
△ 25200200	SUPPLEMENTAL WATERING		UNIT	7	7	
28000400	PERIMETER EROSION BARRIER		FOOT	200	200	
28000510	INLET FILTERS		EACH	19	19	
35101800	AGGREGATE BASE COURSE, TYPE B 6"		SQ YD	1493	1493	
* 40201000	AGGREGATE FOR TEMPORARY ACCESS		TON	20	20	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING		TON	24	24	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH		SQ FT	7966	7966	
* 44000100	PAVEMENT REMOVAL		SQ YD	622	622	
44000300	CURB REMOVAL		FOOT	230	230	
44000600	SIDEWALK REMOVAL		SQ FT	5426	5426	
* 50901760	PIPE HANDRAIL		FOOT	66	66	
* 60100915	PIPE DRAINS 6"		FOOT	35	35	
* 60107700	PIPE UNDERDRAINS 6"		FOOT	642	642	
60255500	MANHOLES TO BE ADJUSTED		EACH	6	6	
60257900	MANHOLES TO BE RECONSTRUCTED		EACH	1	1	
* 60600505	CONCRETE CURB (SPECIAL)		FOOT	106	106	
67100100	MOBILIZATION		LSUM	1	1	
△ 81012100	CONDUIT IN TRENCH, 1/2" DIA. PVC		FOOT	925	925	
△ 81012200	CONDUIT IN TRENCH, 3/4" DIA., PVC		FOOT	370	370	
△ 81013200	CONDUIT IN TRENCH, 6" DIA., PVC		FOOT	250	250	
△ 81702100	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12		FOOT	1930	1930	
△ 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10		FOOT	175	175	
△ * 81900302	TRENCH AND BACKFILL WITH SCREENINGS OR SAND		FOOT	1545	1545	
△ * K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT		UNIT	8.21		8.21
△ * K1003455	LANDSCAPE FILL SOIL		CU YD	219	219	
△ * K1005481	SHREDDED BARK MULCH 3"		SQ YD	130	130	
△ * X0321766	LIGHT POLE, SPECIAL (DECORATIVE ORNAMENTAL)		EACH	1	1	
* X0323407	FLAG POLES		EACH	1	1	
△ * X0323950	LUMINAIRE, METAL HALIDE, 175 WATT		EACH	1	1	
* X0325586	MOW STRIP		SQ YD	8	8	
△ * X0327066	IN GRADE FIXTURE FOR UPLIGHTING		EACH	16	16	

• SEE SPECIAL PROVISIONS
 △ SPECIALTY ITEMS

FILE NAME = p:\N0240094\Plans\sheets\ 04 SQQ.dgn
 PLOT DATE = 4/22/2011 11:02:37 AM

DESIGNED - K.L.R.	REVISED -
DRAWN - K.L.R.	REVISED -
CHECKED - S.M.W.	REVISED -
DATE - 4-11	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE : NONE SHEET NO. 4 OF 40 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00243-02-LS	MCLEAN	40	4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 91461	