

GENERAL NOTES

1. ALL ELEVATIONS SHOWN ON THE PLANS ARE BASED ON THE CHICAGO CITY DATUM. THE CONVERSION EQUATION FROM CCD TO NAVD 88 IS: NAVD 88 ELEVATION=CCD + 579.19.
2. ALL DIMENSIONS SHOWN ON THE PLANS ARE TO THE EDGE OF PAVEMENT UNLESS OTHERWISE NOTED.
3. ALL DIMENSIONS ARE IN FEET UNLESS OTHERWISE NOTED.
4. THE CONTRACTOR SHALL VERIFY THE STRUCTURE DECK ELEVATIONS IN THE PLANS WHERE THE FIXED SPANS OF THE BASCULE BRIDGE MEET THE ADJACENT EXISTING BRIDGES AS WELL AS THE MOVABLE BRIDGE AND VERIFY ELEVATION CORRELATIONS TO THE ENGINEER PRIOR TO DECK REMOVAL AND DECK REPLACEMENT. THIS WORK SHALL BE INCLUDED IN THE COST FOR CONSTRUCTION LAYOUT.
5. SAW CUTTING OR MEDIAN REMOVAL (GRINDING) WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE OF THE ADJACENT REMOVAL ITEM.
6. THE CONTRACTOR SHALL EXERCISE DUE CARE AND COORDINATE CONSTRUCTION ACTIVITIES WITH THE RESPECTIVE UTILITIES BEFORE STARTING ANY EXCAVATION/REMOVAL. THE CONTRACTOR SHALL CALL THE CHICAGO UTILITY ALERT NETWORK (C.U.A.N.) AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRICAL, TELEPHONE, CABLE, AND GAS FACILITIES (48 HOURS NOTIFICATION IS REQUIRED). THE CONTRACTOR SHALL CONTACT THE CITY OF CHICAGO DEPARTMENT OF WATER MANAGEMENT AT (312) 747-7893 AND MWRD AT (312) 751-5600 FOR WATER AND SEWER LOCATIONS.
7. THE CHICAGO TRANSIT AUTHORITY HAS EXISTING AND/OR ABANDONED FACILITIES IN THE AREA. SUCH FACILITIES MAY INCLUDE ELEVATED RAIL TRACKS, SUBWAYS, UNDERGROUND DUCT LINES, AND/OR FORMER STREETCAR TRACKS. COPIES OF DRAWINGS WILL BE SUBMITTED TO THE OUC OFFICE. CAUTION SHOULD BE EXERCISED WHEN EXCAVATING NEAR STREETCAR TRACKS. MEMBERS OF THE CHICAGO AREA JOINT ELECTROLYSIS COMMITTEE MAY USE STREETCAR TRACKS AND NEGATIVE CABLE. PLEASE CONTACT MR. YOUSEF TABIB OF COMED BEFORE CUTTING OR REMOVING ANY BURIED STREETCAR RAILS. HE MAY BE REACHED AT (630) 576-6952. THE CONTRACTOR SHALL ALSO COORDINATE WITH MR. DAVID HEARD AT 312-681-3862 FOR TRANSIT TUNNELS AND ADJACENT APPURTENANCES.
8. SHOULD ARTIFICIAL LIGHTING BE USED IN NIGHT OPERATIONS THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC, MARINE TRAFFIC ON THE RIVER, AND ADJOINING COMMERCIAL AND RESIDENTIAL AREAS.
9. THE CONTRACTOR SHALL NOT BE ALLOWED TO SET UP A YARD, STAGING AREA OR FIELD OFFICE ON STATE OR CITY PROPERTY WITHOUT WRITTEN PERMISSION FROM IDOT OR THE CITY OF CHICAGO.
10. LOCAL ROADS, DRIVEWAYS AND PROPERTY ACCESS DRIVES ADJACENT TO CONGRESS PARKWAY (S. TILDEN STREET, WACKER DRIVE) MUST REMAIN OPEN TO TRAFFIC AT ALL TIMES DURING CONSTRUCTION. SHOULD A TEMPORARY CLOSURE BE NECESSARY, THE CONTRACTOR SHALL NOTIFY THE STATE AND THE AFFECTED PROPERTY OWNER TWENTY-FOUR (24) HOURS IN ADVANCE OF SUCH CLOSURE. CONSTRUCTION ACTIVITIES SHALL BE EXPEDITED AND ACCESS RESTORED WITHIN AN ADEQUATE TIME FRAME AS DIRECTED BY THE ENGINEER.
11. ANY ELECTRICAL SYSTEMS OR UNITS DAMAGED DURING CONSTRUCTION, BUT NOT INCLUDED IN THE CONTRACT FOR REPLACEMENT OR REHABILITATION SHALL BE REPAIRED OR REPLACED AT THE CONTRACTORS EXPENSE TO THE SATISFACTION OF THE ENGINEER.
12. THE CONTRACTOR SHALL BE REQUIRED TO OBTAIN ALL APPLICABLE CITY PERMITS. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT INCLUDED IN THE COST OF THE CONTRACT.
13. EXISTING BRIDGE DECK, PAVEMENT, SIDEWALKS, EMBANKMENT, DRAINAGE SYSTEM COMPONENTS, GUARDRAILS OR HIGHWAY APPURTENANCES DAMAGED DURING CONSTRUCTION, BUT NOT SHOWN TO BE REMOVED ON THE PLANS, SHALL BE REPLACED OR REPAIRED AT THE CONTRACTOR'S EXPENSE. THIS WORK SHALL MEET WITH THE APPROVAL OF THE ENGINEER.
14. DURING CONSTRUCTION, EMERGENCY VEHICLE ACCESS WILL BE MAINTAINED TO THE EXPRESSWAY, RAMPS, ADJACENT SIDE ROADS AND THE SOUTH BRANCH OF THE CHICAGO RIVER. IN ADDITION RAMPS TEMPORARILY CLOSED DURING THE STAGING OF THE PROJECT (I-90/94, WACKER DRIVE AND FRANKLIN STREET) WILL REMAIN ACCESSIBLE TO EMERGENCY VEHICLES AT ALL TIMES. THIS WORK WILL NOT BE PAID SEPARATELY, BUT INCLUDED IN THE COST FOR TRAFFIC CONTROL AND PROTECTION (EXPRESSWAY).
15. AN ESTIMATED DECK SLAB REPAIR (PARTIAL) QUANTITY HAS BEEN INCLUDED IN THE CONTRACT TO ACCOMMODATE THE MAINTENANCE OF THE BRIDGE DECKS WITHIN THE TRAFFIC CONTROL PLAN LIMITS WHICH MAY SHOW SIGNS OF DETERIORATION. THE ENGINEER WILL DETERMINE ANY AREAS TO BE PATCHED AND THE WORK SHALL BE DONE TO THE SATISFACTION OF THE ENGINEER. THIS WORK INCLUDES SAW CUTTING, PARTIAL DEPTH DECK REMOVAL AND REPAIR AND WILL BE PAID AT THE CONTRACT UNIT PRICE FOR PER SQUARE YARD FOR DECK SLAB REPAIR (PARTIAL).
16. TWO WEEKS PRIOR TO PLACING PERMANENT PAVEMENT MARKINGS THE CONTRACTOR SHALL CONTACT IDOT AREA TRAFFIC FIELD ENGINEER DON CHIARUGI AT 847 741-9857.
17. THE ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470, IDOT COMMUNICATIONS CENTER AND ILLINOIS EMERGENCY PATROL, 72 HOURS PRIOR TO PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.
18. THE CONTRACTOR SHALL SECURE THE END OF THE EXISTING BRIDGE EXPANSION JOINT TO THE DECK LEVEL AT THE AREA OF MEDIAN REMOVAL AT APPROXIMATE STA. 383+90. THIS WORK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER SQUARE FOOT FOR CONCRETE MEDIAN REMOVAL AND SHALL BE PERFORMED TO THE SATISFACTION OF THE ENGINEER. AT THE COMPLETION OF THE PROJECT THE CONTRACTOR SHALL UNSECURE THE JOINT TO ORIGINAL CONDITION. THIS WORK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER SQUARE FOOT FOR CONCRETE MEDIAN (SPECIAL) AND SHALL BE PERFORMED TO THE SATISFACTION OF THE ENGINEER.
19. THE CONTRACTOR SHALL VERIFY THE PRESENCE/LOCATION OF CONDUIT IN THE SIDEWALK ON STRUCTURE SN 016-460 AND SN 016-0458 AND EXERCISE DUE CARE DURING THE INSTALLATION OF GUARDRAIL, TRAFFIC SIGNALS, TRAFFIC GATES AND BARRIER GATES. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT INCLUDED IN THE COST OF THE VARIOUS ITEMS LISTED.

☐ INCIDENTAL ITEMS

PB Americas, Inc.
230 WEST MONROE STREET,
SUITE 900
CHICAGO, IL. 60606

USER NAME = #USER#	DESIGNED - DM	REVISED -
FILE NAME = #FILENAME#	DRAWN - MS	REVISED -
PLOT SCALE = #SCALE#	CHECKED - DS	REVISED -
PLOT DATE = 5/7/2009	DATE - 5/08/09	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**CONGRESS PARKWAY OVER SOUTH BRANCH OF THE CHICAGO RIVER
GENERAL NOTES**

SCALE: NONE SHEET NO. 3 OF 83 SHEETS STA. 377+01.00 TO STA. 382+45.28

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
389	2424-2B-R	COOK	398	3
CONTRACT NO. 60D61				
<small>FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT</small>				