

PROJECT: FAP 389 - CONGRESS PARKWAY OVER SOUTH BRANCH OF CHICAGO RIVER - CONTRACT NO. 60D61 COOK COUNTY

X075-2A

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	ROADWAY LIGHTING	80% FED	80% FED	80% FED
				80% FED 20% STATE 1000	80% FED 20% STATE Y030-1E	20% STATE	20% STATE	20% STATE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	9	9				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	61	61				
20101100	TREE TRUNK PROTECTION	EACH	6	6				
20200100	EARTH EXCAVATION	CU YD	50	50				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	75	75				
20400800	FURNISHED EXCAVATION	CU YD	140	140				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	4			4		
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	70	70				
21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	100	100				
25000115	SEEDING, CLASS 1B	ACRE	0.22	0.22				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	20	20				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	20	20				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	20	20				
25002300	TEMPORARY SEEDING	ACRE	0.30	0.30				
25100105	MULCH, METHOD 1	ACRE	0.30	0.30				
25200200	SUPPLEMENTAL WATERING	UNIT	5	5				
28000400	PERIMETER EROSION BARRIER	FOOT	305	305				
28000510	INLET FILTERS	EACH	22	22				
28100101	STONE RIPRAP, CLASS A1	SQ YD	9	9				
28200200	FILTER FABRIC	SQ YD	16	16				
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	334	334				
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	52	52				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	280	280				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	31.0	31.0				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	55	55				
44001500	BRIDGE SIDEWALK REMOVAL	SQ FT	3,878			3,878		
48101100	AGGREGATE SHOULDERS, TYPEA 12"	SQ YD	144	144				
50104800	REMOVAL OF EXISTING CONCRETE DECK	L SUM	1			1		
50157300	PROTECTIVE SHIELD	SQ YD	1,707			1,707		
50200100	STRUCTURE EXCAVATION	CU YD	5.5			5.5		
50300225	CONCRETE STRUCTURES	CU YD	15.5	13.8		1.7		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	508			508		
50300260	BRIDGE DECK GROOVING	SQ YD	988			988		
50300300	PROTECTIVE COAT	SQ YD	2,231	720		1,511		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1		

**PB Americas, Inc.**  
230 WEST MONROE STREET,  
SUITE 900  
CHICAGO, IL. 60606

USER NAME = #USER#  
FILE NAME = #FILENAME#  
PLOT SCALE = #SCALE#  
PLOT DATE = 5/7/2009

DESIGNED - DM  
DRAWN - MS  
CHECKED - DS  
DATE - 5/08/09

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**CONGRESS PARKWAY OVER SOUTH BRANCH OF THE CHICAGO RIVER  
SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. 4 OF 83 SHEETS STA. 377+01.00 TO STA. 382+45.28

F.A.P. RTE. 389	SECTION 2424-2B-R	COUNTY COOK	TOTAL SHEETS 398	SHEET NO. 4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60D61	