F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(57-22)BR-2	MCLEAN	42	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 70671

SCHEDULE OF QUANTITIES

STA.	Ex. CL Elev.	Theor. Top of Ex. PCC @-5" & Var.	Prop. CL Elev.	Prop Top of Binder @-1 3/4"	Pr. Binder Thickness Feet	Pr. Binder Thickness Inches	Binder Tons	Surface Tons	HMA Surf. Rem. Var. Dp. SqYd	HMA Surf. Rem. Spl. SqYd	HMA Shoulders Tons	Approach Slab Rem. SqYd	Br. Approach Pavt. Spl. SqYd	Bit Prime 0.1 Gal/SqYd	Shoulder Rumble Strip Feet
1035+00.00	761.00	760.58	761.00	760.85	0.27	3.25	5.84	3.27	33.33	22.22	1.87			8.89	12.50
1035+12.50	760.79	760.37	760.77	760.62	0.25	3.01	5.51	3.27	33.33	22.22	1.87			8.89	12.50
1035+25.00	760.58	760.16	760.55	760.40	0.24	2.89	5.28	3.27	33.33	22.22	1.87			8.89	12.50
1035+37.50	760.37	759.95	760.33	760.18	0.23	2.77	5.06	3.27	33.33	22.22	1.87			8.89	12.50
1035+50.00	760.17	759.75	760.12	759.97	0.22	2.65	5.06	3.27	33.33	22.22	1.87			8.89	12.50
1035+62.50	759.96	759.54	759.92	759.77	0.23	2.77	5.17	3.27	33.33	22.22	1.87			8.89	12.50
1035+75.00	759.76	759.34	759.72	759.57	0.23	2.77	5.39	3.27	33.33	22.22	1.87			8.89	12.50
1035+87.50	759.55	759.13	759.53	759.38	0.25	3.01	5.73	3.27	33.33	22.22	1.87			8.89	12.50
1036+00.00	759.35	758.93	759.34	759.19	0.26	3.13	6.18	3.27	33.33	22.22	1.87			8.89	12.50
1036+12.50	759.14	758.72	759.16	759.01	0.29	3.49	6.74	3.27	33.33	22.22	1.87			8.89	12.50
1036+25.00	758.94	758.52	758.98	758.83	0.31	3.73	7.63	3.27	33.33	22.22	1.87			8.89	12.50
1036+37.50	758.71	758.29	758.81	758.66	0.37	4.45	7.63	3.27	33.33	22.22	1.87			8.89	12.50
1036+50.00	758.61	758.19	758.65	758.50	0.31	3.73	6.88	3.27	33.33	22.22	1.87			8.89	12.50
1036+62.50	758.46	758.04	758.49	758.34	0.30	3.64	6.71	3.27	33.33	22.22	1.87			8.89	12.50
1036+75.00	758.31	757.89	758.33	758.18	0.30	3.55	6.22	3.27	33.33	22.22	1.87			8.89	12.50
1036+87.50	758.15	757.78	758.19	758.04	0.26	3.12	5.67	3.27	33.33	22.22	1.87			8.89	12.50
1037+00.00	758.00	757.66	758.05	757.90	0.25	2.96	5.14	3.27	33.33	22.22	1.87			8.89	12.50
1037+12.50	757.87	757.55	757.91	757.76	0.21	2.55	4.50	3.27	33.33	22.22	1.87			8.89	12.50
1037+25.00	757.74	757.44	757.78	757.63	0.19	2.27	4.09	3.27	33.33	22.22	1.87			8.89	12.50
1037+37.50	757.60	757.34	757.66	757.51	0.18	2.11	3.78	3.27	33.33	22.22	1.87			8.89	12.50
1037+50.00	757.47	757.23	757.54	757.39	0.16	1.95	3.40	3.27	33.33	22.22	1.87			8.89	12.50
1037+62.50	757.36	757.14	757.43	757.28	0.14	1.69	0.73	1.50	15.33	10.22	0.86			4.09	5.75
1037+68.25	757.30	757.10	757.38	6'-0" Flexible Connector			118.36	70.10	715.33	476.89	40.06			190.76	268.25
1037+74.25	757.25	757.06	757.32												
1037+75.00	757.24														
1037+87.50	757.13														
1038+00.00	757.01														
1038+04.25	757.09	Omission Form Resurfacing Sta.1037+68.3 to Sta.1040+31.8													
1038+65.54	756.72														
1039+34.46	756.47														
1039+95.75	756.40														
1040+00.00	756.42														
1040+12.50	756.45														
1040+25.00	756.49														
1040+25.75	756.53	756.34	756.43	6'-0" Flexible Connector											
1040+31.80	756.53	756.41	756.43				0.26	15.20	10.13	0.85				2.53	5.70
1040+37.50	756.53	756.32	756.43	NO BINDER SURFACE ONLY Sta. 1040+25.75 to Sta. 1041+00.00			2.51	33.33	22.22	1.87				5.56	12.50
1040+50.00	756.56	756.32	756.45				2.87	33.33	22.22	1.87				5.56	12.50
1040+62.50	756.60	756.34	756.48				3.23	33.33	22.22	1.87				5.56	12.50
1040+75.00	756.63	756.34	756.51				3.81	33.33	22.22	1.87				5.56	12.50
1040+87.50	756.67	756.35	756.55				4.39	33.33	22.22	1.87				5.56	12.50
1041+00.00	756.70	756.36	756.60	756.45	0.10	1.16	2.56	3.27	33.33	22.22	1.87			8.89	12.50
1041+12.50	756.74	756.37	756.65	756.50	0.13	1.59	3.48	3.27	33.33	22.22	1.87			8.89	12.50
1041+25.00	756.77	756.38	756.70	756.55	0.18	2.14	4.14	3.27	33.33	22.22	1.87			8.89	12.50
1041+37.50	756.85	756.43	756.77	756.62	0.19	2.29	4.16	3.27	33.33	22.22	1.87			8.89	12.50
1041+50.00	756.92	756.50	756.83	756.68	0.18	2.17	3.83	3.27	33.33	22.22	1.87			8.89	12.50
1041+62.50	757.02	756.60	756.91	756.76	0.16	1.93	3.38	3.27	33.33	22.22	1.87			8.89	12.50
1041+75.00	757.12	756.70	756.99	756.84	0.14	1.69	2.93	3.27	33.33	22.22	1.87			8.89	12.50
1041+87.50	757.22	756.80	757.07	756.92	0.12	1.45	2.59	3.27	33.33	22.22	1.87			8.89	12.50
1042+00.00	757.32	756.90	757.16	757.01	0.11	1.33	2.48	3.27	33.33	22.22	1.87			8.89	12.50
1042+12.50	757.42	757.00	757.26	757.11	0.11	1.33	2.48	3.27	33.33	22.22	1.87			8.89	12.50
1042+25.00	757.52	757.10	757.36	757.21	0.11	1.33	2.59	3.27	33.33	22.22	1.87			8.89	12.50
1042+37.50	757.62	757.20	757.47	757.32	0.12	1.45	2.93	3.27	33.33	22.22	1.87			8.89	12.50
1042+50.00	757.72	757.30	757.59	757.44	0.14	1.69	3.49	3.27	33.33	22.22	1.87			8.89	12.50
1042+62.50	757.81	757.39	757.71	757.56	0.17	2.05	4.05	3.27	33.33	22.22	1.87			8.89	12.50
1042+75.00	757.91	757.49	757.83	757.68	0.19	2.29	4.61	3.27	33.33	22.22	1.87			8.89	12.50
1042+87.50	758.01	757.59	757.96	757.81	0.22	2.65	5.39	3.27	33.33	22.22	1.87			8.89	12.50
1043+00.00	758.11	757.69	758.10	757.95	0.26	3.13									
							55.11	69.33	715.20	476.80	40.05			172.53	268.20

West Approach Pavement Sta. 1037+74.25 to Sta. 1038+04.25 — 133.33 — 138.55

Bridge Deck Sta. 1039+04.25 to Sta. 1039+95.75

East Approach Pavement Sta. 1039+95.75 to Sta. 1040+25.75 — 133.33 — 138.55

West Appr. / Bk. W. Abut. / CL Pier 1 / CL Pier 2 / Bk. E. Abut. / East Appr.

	Binder Tons	Surface Tons	HMA Surf. Rem. Var. Dp. SqYd	HMA Surf. Rem. Spl. SqYd	HMA Shoulders Tons	Approach Slab Rem. SqYd	Br. Approach Pavt. Spl. SqYd	Bit Prime Gal.	Shoulder Rumble Strip Feet	
TOTALS	173.47	139.43	1430.53	953.69	80.11	266.67	277.09	363.29	536.45	x2
USE	174.00	140.00	1431.00	954.00	81.00	267.00	278.00	364.00	1073.00	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

KICKAPOO CREEK

STR# 057-0126 (WB I-74)

SCALE: DRAWN BY

DATE CHECKED BY