

# EARTHWORK SCHEDULE

20200100

LOCATION	EARTH EXCAVATION	EARTH EXC ADJ SHRINK 25%	EMBANKMENT (FILL)	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
<b>MAINLINE (IL RTE 78)</b>				
901+75 - 902+50	47.8	35.9	14.7	21.1
902+50 - 908+50	1,431.4	1,073.5	394.2	679.4
908+50 - 914+50	755.5	566.6	879.4	-312.8
914+50 - 917+80	481.1	360.8	365.9	-5.1
<b>ENTRANCES/SIDEROADS</b>				
MIT Entrance				
98+20.79 - 99+75	275.0	206.3	0.2	206.1
French Creek Road				
100+75 - 101+75	198.8	149.1	37.0	112.1
<b>TOTAL</b>	<b>3,189.5</b>	<b>2,392.1</b>	<b>1,691.4</b>	<b>700.7</b>
<b>TOTAL (ROUNDED TO 5 CY)</b>	<b>3,190</b>			

# SIGNING SCHEDULE FOR MULTI-USE PATH

SIGN PANEL QUANTITY (EACH)	WOOD SIGN SUPPORT QUANTITY (EACH)	TYPE OF SIGN PANEL	SIZE OF SIGN PANEL	SURFACE AREA FOR ONE PANEL (SQ FT)	72000100	73000100
					SIGN PANEL - TYPE 1 (SQ FT)	WOOD SIGN SUPPORT (2) (FOOT)
3	3	R1-1	18" X 18"	2.25	6.75	48
3		R15-8	18" X 9"	1.13	3.38	
4	4	R5-3	24" X 24"	4.00	16.00	64
1	1	W1-6	24" X 12"	2.00	2.00	16
1	1	W1-7	24" X 12"	2.00	2.00	16
2	2	W3-1	18" X 18"	2.25	4.50	32
4	4	W11-15	36" X 36"	9.00	36.00	64
2		W16-9P	30" X 9"	1.88	3.75	
2		W16-7P	21" X 15"	2.19	4.38	
2	2	D11-1	24" X 18"	3.00	6.00	32
2		M6-4	21" X 15"	2.19	4.38	
100% STATE SUB-TOTAL					72	218
20% CITY OF MORRISON SUB-TOTAL					18	54
GRAND TOTAL					90	272

**NOTES:**

- 1). SEE "MULTI-USE PATH SIGNING DETAIL" FOR EXACT LOCATIONS.
- 2). EACH SIGN SUPPORT SHALL BE 16 FEET IN LENGTH.