

HOT-MIX ASPHALT SCHEDULE

48203023

48300300

X4060110

Z0028415

LOCATION	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	PORTLAND CEMENT CONCRETE SHOULDERS 8"	BITUMINOUS MATERIALS (PRIME COAT)	GEOTECHNICAL REINFORCEMENT
STATION TO STATION	SQ YD	SQ YD	POUND	SQ YD
IL RTE 78 MAINLINE				
Lt & Rt Sta 901+97.00 - 902+42.00	---	---	81.4	---
Lt & Rt Sta 902+42.00 - 905+89.71	---	---	638.0	---
Lt & Rt Sta 905+89.71 - 909+25.00	---	---	615.4	---
Lt & Rt Sta 909+25.00 - 909+32.96	---	---	14.3	---
Lt & Rt Sta 909+32.96 - 911+01.04	---	---	---	---
Lt & Rt Sta 911+01.04 - 913+93.00	---	---	560.8	---
Lt & Rt Sta 913+93.00 - 914+20.00	---	---	51.7	---
Lt & Rt Sta 914+20.00 - 917+80.00	---	---	684.4	---
SHOULDERS				
Lt Sta 901+97.00 - 905+89.71	133.4	---	---	---
Rt Sta 901+97.00 - 905+89.71	133.2	---	---	---
Lt Sta 905+89.71 - 99+25.78	37.0	---	25.0	51.9
Rt Sta 905+89.71 - 101+55.56	76.3	---	51.5	104.3
Lt Sta 908+17.28 - 909+26.00	112.3	---	75.8	---
Lt Sta 909+12.49 - 909+28.61	---	14.7	---	---
Rt Sta 909+12.49 - 909+37.30	---	22.7	---	---
Rt Sta 909+12.49 - 909+59.29	---	---	---	---
Lt Sta 909+12.49 - 99+34.93	299.7	---	202.3	347.2
Rt Sta 909+12.49 - 101+55.56	295.3	---	199.3	352.6
Rt Sta 910+84.53 - 911+06.60	---	---	---	---
Lt Sta 910+93.58 - 912+06.19	101.9	---	68.8	---
Lt Sta 910+96.21 - 917+34.58	644.5	---	435.0	---
Rt Sta 911+06.60 - 917+80.00	645.6	---	435.8	---
Rt Sta 911+75.00 - 914+00.00	---	---	---	---
Lt Sta 913+00.00 - 913+75.00	---	---	---	---
BIKEPATH/ENTRANCES/SIDEROADS				
Lt Sta 98+20.79 - 908+17.28	---	---	133.58	---
Lt & Rt Sta 99+02.24 - 99+87.48	---	---	144.90	322.0
Lt Sta 99+02.24 - 99+34.93	---	---	---	11.8
Rt Sta 99+02.24 - 99+25.78	---	---	---	8.9
Lt & Rt Sta 100+12.39 - 101+55.56	---	---	319.37	709.7
Rt Sta 902+53.00	---	---	---	---
Lt Sta 903+20.00	---	---	56.61	---
Lt Sta 912+06.19 - 913+42.50	---	---	68.14	---
Lt Sta 913+42.50 - 916+63.34	---	---	160.18	---
Lt Sta 916+63.34	---	---	---	---
Rt Sta 916+63.34	---	---	---	---
Rt Sta 914+60.00 - 916+92.00	---	---	148.77	---
Rt Sta 917+03.72	---	---	103.16	---
Rt Sta 917+15.39 - 917+20.44	---	---	---	---
100% STATE SUB-TOTAL	2,436	37	5,143	1,908
20% CITY OF MORRISON SUB-TOTAL	43	---	131	---
GRAND TOTAL	2,479	37	5,274	1,908