

PAVEMENT MARKING SCHEDULE										
LOCATION	LENGTH	POLYUREA PVMT MARKING 4"		POLYUREA PVMT MARKING 6"	PREFORMED PLASTIC PVMT MARK TYPE B, 6"	GROOVING FOR RECESSED PVMT MARKING, 7"	POLYUREA PVMT MARK 24" WHITE	RAISED REFLECTIVE PAVEMENT MARKERS		RAISED REFLECTIVE PVMT MARK REM EACH
		WHITE	YELLOW	WHITE	WHITE			TWO-WAY AMBER EACH	ONE-WAY CRYSTAL EACH	
		FOOT	FOOT	FOOT	FOOT					
STA 282+40 TO 429+60	14720	29440	29440		7360	7360		368	184	552
429+60 TO 484+50	5490		10980	904	2745	2745	208	137	69	206
SUBTOTAL		29440	40420	904	10105	10105	208	505	253	758
TOTAL		69860		904	10105	10105	208	758		758

TEMPORARY PAVEMENT MARKING SCHEDULE							
LOCATION	LENGTH	TEMPORARY PVMT MARKING 4"		TEMPORARY PVMT MARK 6"	TEMPORARY PVMT MARK 24"	SHORT TERM PVMT MARK FOOT	WORK ZONE PVMT MARK REM FOOT
		WHITE	YELLOW	WHITE	WHITE		
		FOOT	FOOT	FOOT	FOOT		
STA 282+40 TO 429+60	14720	29440	29440	7360		5888	1963
429+60 TO 484+50	5490		10980	3649	208	2196	732
SUBTOTAL		29440	40420	11009	208	8084	2695
TOTAL		69860		11009	208	8084	2695

DETECTOR LOOPS		
	DETECTOR LOOP TYPE I	DETECTOR LOOP TESTING
	FOOT	EACH
DIVISION ST	1200	1
3RD ST	825	1
TOTAL	2025	2