

CONSTR. CODE
100% STATE

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | ROADWAY |
|----------|---|-------|----------------|------------|
| | | | | 0005 URBAN |
| 42400100 | PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH | SO FT | 6738 | 6738 |
| 42400800 | DETECTABLE WARNINGS | SO FT | 784 | 784 |
| 44000155 | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" | SO YD | 84944 | 84944 |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SO YD | 39350 | 39350 |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 1054 | 1054 |
| 44000600 | SIDEWALK REMOVAL | SO FT | 5661 | 5661 |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 2910 | 2910 |
| 60255500 | MANHOLES TO BE ADJUSTED | EACH | 4 | 4 |
| 60603800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 | FOOT | 569 | 569 |
| 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 572 | 572 |
| 66700205 | PERMANENT SURVEY MARKERS, TYPE I | EACH | 10 | 10 |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 | 1 |

• SPECIALTY ITEMS

| | | | | | | | | | | | | | | | |
|-------------------------------------|------------------------------|------------|-----------|---|------------------------------|-------|----|--------|-------------|---------|--------|-------------------------|-----------|----|---|
| FILE NAME = | USER NAME = awpernterdy | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | | | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | | |
| e:\pwork\pjd\dot\carpentard\0250245 | 3566902-shc-500.dgn | DRAWN - | REVISED - | | SCALE: | SHEET | OF | SHEETS | STA. | TO STA. | 332 | 62,6RS-3;7 RS-4;TR-RS-2 | KANKAKEE | 17 | 4 |
| | PLOT SCALE = 1/8" = 1' / in. | CHECKED - | REVISED - | | CONTRACT NO. 66802 | | | | | | | | | | |
| | PLOT DATE = 6/11/2014 | DATE - | REVISED - | | ILLINOIS FED. AID PROJECT | | | | | | | | | | |