

CONSTR. CODE
100% STATE
ROADWAY
0005
RURAL

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
20200100	EARTH EXCAVATION	CU YD	671	671
20400800	FURNISHED EXCAVATION	CU YD	2958	2958
25000200	SEEDING, CLASS 2	ACRE	8.21	8.21
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	739	739
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	739	739
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	739	739
25100115	MULCH, METHOD 2	ACRE	8.21	8.21
25100630	EROSION CONTROL BLANKET	SQ YD	1971	1971
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1642	1642
28000305	TEMPORARY DITCH CHECKS	FOOT	171	171
28100105	STONE RIPRAP, CLASS A3	SQ YD	68	68
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	600	600
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	34	34
40600545	LEVELING BINDER (HAND METHOD), N90	TON	56	56

14

△ SPECIALTY ITEMS

FILE NAME :	USER NAME : duncanbd	DESIGNED -	REVISED -
o:\p\work\p\p\dot\duncanbd\0315512\0366\CS3-44-SDD.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 1 OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5T	138-31RS-2	ILLINOIS	186	3
CONTRACT NO. 66C53			ILLINOIS FED. AID PROJECT	