

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE	ROADWAY
				0005	RURAL
40600895	CONSTRUCTING TEST STRIP	EACH	2		2
40600990	TEMPORARY RAMP	SQ YD	1681		1681
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	29087		29087
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	9389		9389
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	14602		14602
44000300	CURB REMOVAL	FOOT	120		120
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	232		232
44213000	PATCHING REINFORCEMENT	SQ YD	832		832
44213200	SAW CUTS	FOOT	2898		2898
44213204	TIE BARS 3/4"	EACH	112		112
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5041		5041
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	367		367
48203100	HOT-MIX ASPHALT SHOULDERS	TON	16861		16861
50104400	CONCRETE HEADWALL REMOVAL	EACH	1		1

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -
c:\pe-work\pdat\duncanbd\0315542\036653-ent-SD0.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 8/10/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE:	SHEET 2 OF SHEETS	STA.	TO STA.	F.A.I. RTE. 57	SECTION 138-31RS-2	COUNTY IROQUOIS	TOTAL SHEETS 186	SHEET NO. 4
				CONTRACT NO. 66C53				
				ILLINOIS FED. AID PROJECT				