

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE	
				ROADWAY	
				0005	RURAL
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	71242		71242
66500105	WOVEN WIRE FENCE, 4'	FOOT	4356		4356
66501100	WOVEN WIRE GATES, 4' X 12' SINGLE	EACH	2		2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8		8
67100100	MOBILIZATION	L SUM	1		1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4		4
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	150		150
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16		16
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1496		1496
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	250168		250168
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	9340		9340
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1505		1505
△ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	87376		87376
△ 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3978		3978

△

△

△

△ SPECIALTY ITEMS

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\duncanbd\00315542\036	CS3-shr-500.dgn	DRAWN -	REVISED -		57	(38-3)RS-2	IRROUOIS	186	6				
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		SCALE: SHEET 4 OF SHEETS STA. TO STA.				CONTRACT NO. 66C53				
	PLOT DATE = 6/10/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								