CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 100% STATE ROADWAY 0005 RURAL
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	23677	23677
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	16	16
40600535	LEVELING BINDER (HAND METHOD), N70	TON	26	26
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5893	5893
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	400	400
42400800	DETECTABLE WARNINGS	SQ FT	80	80
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	52615	52615
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	64	64
44000600	SIDEWALK REMOVAL	SQ FT	400	400
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	64	64
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1

14

* SPECIALTY ITEMS

* INTERMITTENT SPRING ROAD REPAIR 2014-6

FILE NAME = c:\pw_work\pwidot\carpenterdj\d0397081\D-xxxx-xht-S00.dgn	USER NAME = carpenterdj	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 6/25/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	*	KANKAKEE	10	3

CONTRACT NO. 66D91

ILLINOIS FED. AID PROJECT