

LOCATION OF WORK:	FAP 704 (I-55BUSN/VET' S PKWY)	S. N. 057-0063	S. N. 057-0064
	URBAN MULTILANE	URBAN MULTILANE	URBAN MULTILANE
	OTHER PRINCIPAL ARTERIAL	OTHER PRINCIPAL ARTERIAL	OTHER PRINCIPAL ARTERIAL
	STA. 33+30 TO STA. 89+41.79	STA. 47+06.97 TO STA. 49+10.79	STA. 72+79.68 TO STA. 75+96.94
	MCLEAN COUNTY	MCLEAN COUNTY	MCLEAN COUNTY
FUNDING BREAKOUT:	100% STATE	100% STATE	100% STATE
CONSTRUCTION TYPE CODE:	0004	0014	0014

CODE NO.	ITEM	UNIT	TOTAL QUANTITY			
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	730.0	730.0	0.0	0.0
• 78200410	GUARDRAIL MARKERS, TYPE A	EACH	40.0	40.0	0.0	0.0
• 78200530	BARRIER WALL MARKERS, TYPE C	EACH	2.0	0.0	0.0	2.0
• 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6.0	6.0	0.0	0.0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	960.0	175.0	305.0	480.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	510.0	510.0	0.0	0.0
• 88600100	DETECTOR LOOP, TYPE I	FOOT	440.0	440.0	0.0	0.0
X0323586	PIPE DRAIN REMOVAL	FOOT	40.0	40.0	0.0	0.0
X4402400	CURB REMOVAL (SPECIAL)	FOOT	4,150.0	4,150.0	0.0	0.0
X4403300	CONCRETE MEDIAN REMOVAL	SQ FT	17,225.0	17,225.0	0.0	0.0
X4406060	PARTIAL DEPTH REMOVAL, TYPE I, 6"	SQ YD	60.0	60.0	0.0	0.0
X4406070	PARTIAL DEPTH REMOVAL, TYPE I, 7"	SQ YD	50.0	50.0	0.0	0.0
X4406080	PARTIAL DEPTH REMOVAL, TYPE I, 8"	SQ YD	40.0	40.0	0.0	0.0
X4406090	PARTIAL DEPTH REMOVAL, TYPE I, 9"	SQ YD	20.0	20.0	0.0	0.0
• DENOTES SPECIALTY ITEM						

FILE NAME =	USER NAME = dodgens	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
er\p\work\p\dot\dodgens\0267571\0570338-sht-500.dgn	PLOT SCALE = 48,0000' / in.	DRAWN -	REVISED -			704	(57-7)RS-1&1RS-3	McLean	273	13	
MODEL NAME =	PLOT DATE = 8/11/2014	CHECKED -	REVISED -			CONTRACT NO. 70838					
		DATE -	REVISED -			SCALE:	SHEET 7 OF 10 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	