

SCHEDULE OF QUANTITIES

EROSION CONTROL (SHEET 1 OF 3)

DIRECTION	STATION	TO	STATION	OFFSET	TEMPORARY DITCH CHECKS 28000305 (FOOT)	PERIMETER EROSION BARRIER 28000400 (FOOT)	INLET & PIPE PROTECTION 28000500 (EACH)	STONE RIPRAP CLASS A 4 28100107 (SQ YD)	FILTER FABRIC 28200200 (SQ YD)	STONE RIPRAP CLASS A4 (TONS)	BEDDING STONE (TONS)
LEG "A":											
EB	33+30			1.75' Rt.	17.0						
EB	31+00			CL	10.0						
EB	30+50			0.5' LT	15.0						
EB	29+50			0.5' LT	15.0						
EB	29+00			CL	15.0						
WB	32+50			1.0' RT	12.0						
WB	31+50			1.0' RT	10.0						
WB	28+50			1.0' RT	15.0						
WB	28+00			3.0' RT.	15.0						
EB	28+00		26+00	65.0' LT		194.3					
WB	27+50			2.5' RT	12.0						
WB	27+00			3.0' RT	12.0						
WB	26+00			4.5' RT	10.0						
EB	26+00		25+00	65'-71' LT		97.2					
EB	25+00		23+19	71'-68' LT		175.5					
WB	25+00			6.0' RT	6.0						
EB	23+19		23+00	68'-75' LT		19.7					
WB	23+19			5.0' RT.			1.0				
EB	23+00		20+73	75'-68' LT		220.6					
EB	19+06.39			3.44' LT			1.0				
WB	23+00		21+50	62.0' RT		154.0					
WB	21+50		21+05.5	62'-58' RT		45.9					
WB	18+96		18+75.00 BK	68'-70' RT		21.1					
WB	335+55.87 AH.		337+00	70.0' LT		144.1					
EB	335+83		337+00	58.5'-60' RT		116.5					
EB	337+00		356+00	60.0' RT		1900.0					
WB	337+00		338+50	70'-72' LT		150.0					
EB	337+75			4.0' RT.			1.0				
WB	338+50		339+50	72.0' LT		100.0					
EB	339+00			3.0' RT.			1.0				
WB	339+50		341+50	72'-62' LT		200.2					
EB	339+50			5.0' RT.			1.0				
WB	341+50		343+00	62'-60' LT		150.0					
EB	342+50			CL	15.0						
WB	343+00		366+00	60.0' LT		2310.2					
EB	345+50			0.5' RT	15.0						
EB	347+00			0.5' RT	15.0						
EB	348+00			CL	15.0						
EB	349+00			CL	15.0						
EB	349+75			CL	15.0						
WB	350+00			6.0' LT			1.0				
EB	351+00			1.0' RT	15.0						
EB	351+50			0.75' RT	15.0						
WB	352+50			4.0' LT	10.0						
WB	353+10			4.0' LT	10.0						
WB	353+62			1.0' LT			1.0				
WB	353+68			1.0' LT			1.0				
WB	354+50			0.5' LT	15.0						
WB	355+50			1.0' LT	15.0						
WB	356+50			3.5' LT	10.0						
WB	357+00			8.0' LT.			1.0				
EB	357+00			64' RT	12.0						
WB	357+50			4.0' LT	10.0						
EB	358+00			63.0' RT	6.0						
WB	358+50			4.0' LT	10.0						
EB	359+00			59.0' RT	8.0						
WB	359+50			0.5' LT	15.0						
EB	360+00			58.0' RT	8.0						
EB	360+50			CL	15.0						
EB	361+00			59.0' RT	6.0						
EB	361+50			CL	15.0						
EB	362+00			61.0' RT	4.0						
EB	362+50			1.0' RT	15.0						
EB	362+75			63.0' RT	4.0						
EB	363+25			64.0' RT	6.0						
EB	363+75			65.0' RT	6.0						
EB	364+25			67.0' RT	6.0						
EB	364+75			70.0' RT	8.0						
EB	365+25			72.0' RT	8.0						
EB	365+58			72.0' RT	8.0						
WB	366+00		366+22	60'-53.5' LT		23.5					
WB	366+12.5			CL			1.0				
SUB-TOTAL =					514.0	6022.8	10.0	0	0	0	0

FILE NAME =	USER NAME = dodgms	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pw\work\p\dot\dodgms\d0267571\0570838-sht-schedules.dgn		DRAWN -	REVISED -			704	(57-7)RS-1&1RS-3	McLean	273	30	
\$MODELNAME\$		CHECKED -	REVISED -			CONTRACT NO. 70838					
	PLOT DATE = 6/11/2014	DATE -	REVISED -			SCALE: SHEET 2 OF 15 SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			