



DIRECTION	LOCATION: LEG "C"			MEDIAN	OUTSIDE	OFFSET	TEMPORARY DITCH CHECKS 28000305 (FOOT)	PERIMETER EROSION BARRIER 28000400 (FOOT)	INLET & PIPE PROTECTION 28000500 (EACH)	STONE RIPRAP CLASS A 4 28100107 (SQ YD)	FILTER FABRIC 28200200 (SQ YD)	STONE RIPRAP CLASS A4 (TONS)	BEDDING STONE (TONS)
	STA.	TO	STA.										
EB	84+50				X	70.5' RT	10.0						
EB	85+50				X	67.0' RT	10.0						
EB	86+54				X	60.0' RT			1.0				
EB	87+00				X	65.5' RT	10.0						
EB	88+50				X	63.0' RT	10.0						
EB	89+31				X	47-66' RT				13.3	13.3	8.9	4.0
WB	87+45.84 AH		88+50.39		X	40.0' LT		104.6					
WB	88+50				X	67.0' LT	10.0						
WB	89+33				X	46-68' LT				14.7	14.7	9.8	4.4

LEGEND

- TEMPORARY DITCH CHECK
- PERIMETER EROSION BARRIER
- INLET AND PIPE PROTECTION
- CONSTRUCTION LIMITS