

	· · · · · · · · · · · · · · · · · · ·
QUANTITIES FOR	CONCRETE PIPES
INSIDE DIAMETER	ESTIMATED
OF PIPE	CLASS SI CONCRETE
0 1	REQUIRED
	20" (500 mm) WIDTH
TNIOUL	
INCH (mm)	CU. YD. (m3)
4" (100)	0.14 (0.11)
6'' (150)	0.16 (0.12)
8" (200)	0.19 (0.14)
10" (250)	0.22 (0.17)
12" (300)	0.25 (0.19)
15" (375)	0.30 (0.23)
18" (450)	0.35 (0.27)
24" (600)	0.45 (0.35)
30'' (750)	0.57 (0.43)
36" (900)	0.69 (0.53)
42" (1050)	0.83 (0.63)
48" (1200)	0.97 (0.74)
54" (1350)	1.12 (0.86)
60" (1500)	1.28 (0.98)

QUANTITIES FOR METAL PIPES									
INSIDE DIAMETER	ESTIMATED								
OF PIPE	CLASS SI CONCRETE								
	REQUIRED								
	20" (500 mm) WIDTH								
INCH (mm)	CU. YD. (m3)								
4" (100)	0.12 (0.09)								
6" (150)	0.14 (0.11)								
8" (200)	0.16 (0.12)								
10" (250)	0.19 (0.14)								
12" (300)	0.21 (0.16)								
15" (375)	0.25 (0.19)								
18" (450)	0.29 (0.22)								
24" (600)	0.38 (0.29)								
30" (750)	0.47 (0.36)								
36" (900)	0.59 (0.45)								
42" (1050)	0.69 (0.53)								
48" (1200)	0.81 (0.62)								
54'' (1350)	0.93 (0.71)								
60'' (1500)	1.05 (0.81)								

GENERAL NOTES

- 1. CLASS SI CONCRETE SHALL BE USED THROUGHOUT.
- 2. WHEN CONCRETE COLLARS ARE USED TO CONNECT PIPES OF DIFFERENT OUTSIDE DIAMETERS, THE CONCRETE COLLAR SHALL BE FORMED USING THE LARGEST OUTSIDE DIAMETER (SEE END VIEW).
- 3. THE WIRE MESH SHALL WEIGH NOT LESS THAN 54#/100 SQ. FT. (2.63 kg/m²).
- 4. WHEN CONCRETE COLLARS ARE CONSTRUCTED ADJACENT TO AN EXISTING CONCRETE STRUCTURE (HEADWALLS, ETC.) EXPANSION BOLTS, SHALL BE USED AND WILL BE PAID FOR AT THE CONTRACT UNIT PRICE, EACH, FOR EXPANSION BOLTS OF THE SIZE SPECIFIED IN THE PLANS.
- 5. CONCRETE COLLARS WILL BE PAID FOR AT THE CONTRACT UNIT PRICE, PER CUBIC YARD (CUBIC METER), FOR CONCRETE COLLARS INCLUDING ALL MATERIAL AND LABOR SPECIFIED TO COMPLETE THE WORK IN PLACE.

Note: All dimensions are in INCHES (millimeters) unless otherwise shown.

					DISTRICT 5 DETAIL NO. 54248510								
FILE NAME =	USER NAME = dodgems	DESIGNED -	REVISED - 12/06					F.A.P.	SECTION	.on	COUNTY	TOTAL SH	1EET
c:\pw_work\pwidot\dodgems\d0267571\D570	338-sht-details.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS CONCRETE COLLAR			704	(57-7)RS-1 8	& 1RS-3	McLean	273	146	
	PLOT SCALE = 40.0000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION							CONTRACT	NO. 708	338
	PLOT DATE = 6/11/2014	DATE -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA. TO STA.	FED. RO	OAD DIST. NO. IL	LLINOIS FED. AID			