




EXISTING LEGEND

- ① EXISTING CONCRETE PAVEMENT, 9"-6"-9"
- ② EXISTING BITUMINOUS OVERLAY (SEE TABLE 1)
- ③ EXISTING LEVELING BINDER (MACHINE METHOD), MIXTURE 'C', 1"
- ③A EXISTING LEVELING BINDER (MACHINE METHOD), MIXTURE 'C', 2"
- ④ EXISTING BITUMINOUS CONCRETE SURFACE COURSE, MIXTURE 'D' (1 1/2")
- ⑤ EXISTING BITUMINOUS CONCRETE BASE COURSE WIDENING 9"
- ⑥ EXISTING BITUMINOUS SHOULDERS, 8"
- ⑦ EXISTING CONCRETE GUTTER, TYPE A
- ⑧ EXISTING AGGREGATE SHOULDERS

PROPOSED LEGEND

- ⑨ PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH
- ⑩ PROPOSED HOT-MIX ASPHALT SURFACE COURSE, MIX C, N50, 1 1/2"
- ⑪ PROPOSED LEVELING BINDER (MACHINE METHOD), N50, 3/4"
- ⑫ PROPOSED PAVEMENT MARKING LINE - 5"
- ⑬ PROPOSED AGGREGATE WEDGE SHOULDER, TYPE B
- ⑭ PROPOSED HMA SHOULDERS, 6 1/2"
- ⑮ PROPOSED EXCAVATING & GRADING SHOULDERS

TABLE 1	
EXISTING BITUMINOUS CONCRETE OVERLAY	
STA TO STA	THICKNESS
743+50 - 861+00	2.5"
861+00 - 914+00	2.5" TO 3"
914+00 - 918+00	3" TO 4"
918+00 - 1014+00	4" TO 5"
1014+00 - 1020+00	5" TO 6"
1020+00 - 1033+00	6" TO 5"
1030+00 - 1037+00	5" TO 2.5"
1037+00 - 1041+00	2.5"



FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -
ct:\pw\work\p\dot\sparksgw\10333796\0672002-sht-typical.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = Jun-13-2014 01:52:40PM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

TYPICAL SECTIONS			
SCALE:	SHEET 7	OF 19 SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
506	(124)RS-2,(125)RS-3	HANCOCK	19	7
				72G02
ILLINOIS FED. AID PROJECT				